



EnCana Oil & Gas (USA) Inc.

EnCana Oil & Gas (USA) Inc. tel: 720-876-5339
370 – 17th Street
Suite 1700
Denver, CO 80202 fax: 720-876-6339

www.encana.com

May 2, 2007

Diana Mason
Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, UT 84114-5801

RE: Big Indian Fed 14-42-30-25
Section 14, T30S R25E
San Juan County, UT

Dear Ms. Mason:

EnCana Oil & Gas (USA) Inc. is requesting approval to directionally drill the subject well per the Utah Department of Natural Resources, Division of Oil, Gas and Mining Applicable Rules R649-3-11. Please find the following information as required for our proposed Big Indian Fed 15-24-30-25 application:

- EnCana Oil & Gas (USA) Inc., JVA Operating Co. Inc. & Tandem Energy Corp. own all oil & gas within 460' of the intended well bore.
- Surface and Bottom Hole located on BLM Lease No. UTU-89097 and within the Bull Horn Unit and the Big Indian (South) Field.
- SESW, Section 14, T30S R25E, San Juan County, Utah.
- Location plat with surface and bottom hole locations attached.
- Request for an Exception Location, JVA and Tandem letter's of consent, Lease and federal unit map attached.
- Proposed Directional Report attached.

EnCana is drilling this well as a directional well do to topographical and geologic conditions above the bottom hole target The BLM is in agreement with both EnCana's surface and bottom hole locations as proposed for the subject well.

If you have any questions or need additional information, I can be reached at (720) 876-5339.

Sincerely,

Jevin Croteau
Regulatory Analyst

Attachment



EnCana Oil & Gas (USA) Inc.

EnCana Oil & Gas (USA) Inc. tel: 720-876-5339
370 – 17th Street
Suite 1700 fax: 720-876-6339
Denver, CO 80202

www.encana.com

May 2, 2007

Mr. John Baza
Utah Division of Oil, Gas & Mining
1594 North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, UT 84114-5801

Re: Exception Location
Big Indian Fed 14-42-30, 25
1109' FSL and 1721' FEL (Bottom Hole)
SESW Sec 14, T30S, R25E
San Juan County, Utah

Dear Mr. Baza;

Pursuant to Rule R649-3-3 of the Oil & Gas Rules and Regulations of the State of Utah, EnCana Oil & Gas (USA) Inc. hereby requests an exception location for the drilling of the captioned well. Rule R649-3-2 requires a well to be located in the center of a forty (40) acre quarter-quarter section, or a substantially equivalent lot or tract, with a tolerance of two hundred (200) feet in any direction from the center.

The above referenced bottom hole location is an exception location under Rule R649-3-2, being outside the center of the SESW of Section 14, T30S, R25E. The attached plat depicts the location for which EnCana wishes permission to drill as well as the deviation from the location which would be in accordance with Rule R649-3-2.

The requested location has been chosen due to topographic and geologic reasons. The Four Hundred Sixty foot (460') radius of the proposed location is on Federal Lease UTU-89097 and is within the established Bull Horn Unit, UTU-81301X. Lease UTU-89097 is owned by EnCana Oil & Gas (USA) Inc., JVA Operating Company, Inc. and Tandem Energy Corporation. The proposed location has been approved by JVA and Tandem as indicated by the enclosed letters of consent.

If you have any questions or need additional information, please contact me at (720) 876-5339.

Sincerely,

Jevin Croteau
Regulatory Analyst

Attachment



EnCana Oil & Gas (USA) Inc.

370 17th Street
Suite 1700
Denver, CO 80202

tel: (303) 623-2300
fax: (303) 623-2400
www.encana.com

CERTIFIED MAIL – 70031680000232649544

April 9, 2007

Tandem Energy Corporation
200 North Loraine, Suite 500
Midland, TX 79701
Attn: Todd M. Yocham

Re: Exception Location Request to Rule 649-3-2
Big Indian Fed 14-42-30-25
BHL – 1109' FSL, 1721' FWL
Section 14-T30S-R25E
San Juan County, Utah

Mr. Yocham:

EnCana Oil & Gas (USA) Inc. has proposed the drilling of the above captioned well. Due to the nature of the well, the location of the well will require an exception to the Utah Oil & Gas Conservation Commission Rule 649-3-2.

The well does fall within the unit boundaries of the Big Indian Unit, and as such, production will be allocated under the terms of that agreement. The location of the well is based upon our geologic understanding of the area, and the well has been positioned in a location that will be most likely to be successful.

In accordance with Rule 649-3-3, please indicate your consent to the location exception of the Big Indian Fed 14-42-30-25 well by signing in the space provided below and returning one signed original to the undersigned. For your convenience, and also to expedite this process, please also send a copy via fax to (720) 876-6361. Please call me at (720) 876-5361 if you have any questions or concerns.

Very truly yours,
ENCANA OIL & GAS (USA) INC.

Oscar Duarte
Land Negotiator


Exception Location for the Big Indian Fed 14-42-30-25 well is hereby approved this 20 day of April, 2007.

By: Todd M. Yocham

Title: Sr. Vice President

Phone: 432-686-7136 ext. 1121

ENCANATM



EnCana Oil & Gas (USA) Inc.

370 17th Street
Suite 1700
Denver, CO 80202

tel: (303) 623-2300
fax: (303) 623-2400
www.encana.com

CERTIFIED MAIL - 7003168000232649551

April 9, 2007

JVA Operating Company, Inc.
P.O. Box 3634
Midland, TX 79702
Attn: Jerry V. Atkinson

Re: Exception Location Request to Rule 649-3-2
Big Indian Fed 14-42-30-25
BHL - 1109' FSL, 1721' FWL
Section 14-T30S-R25E
San Juan County, Utah

Mr. Atkinson:

EnCana Oil & Gas (USA) Inc. has proposed the drilling of the above captioned well. Due to the nature of the well, the location of the well will require an exception to the Utah Oil & Gas Conservation Commission Rule 649-3-2.

The well does fall within the unit boundaries of the Big Indian Unit, and as such, production will be allocated under the terms of that agreement. The location of the well is based upon our geologic understanding of the area, and the well has been positioned in a location that will be most likely to be successful.

In accordance with Rule 649-3-3, please indicate your consent to the location exception of the Big Indian Fed 14-42-30-25 well by signing in the space provided below and returning one signed original to the undersigned. For your convenience, and also to expedite this process, please also send a copy via fax to (720) 876-6361. Please call me at (720) 876-5361 if you have any questions or concerns.

Very truly yours,
ENCANA OIL & GAS (USA) INC.

Oscar Duarte
Land Negotiator

Exception Location for the Big Indian Fed 14-42-30-25 well is hereby approved this 19th day of April, 2007.

By:

Title: President

Phone: (TX) 432-682-1052 (NM) 505-336-1136

FORM 3

AMENDED REPORT ☐
(highlight changes)

APPLICATION FOR PERMIT TO DRILL						5. MINERAL LEASE NO: UTU-89097		6. SURFACE: Federal	
1A. TYPE OF WORK:								7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>									
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>								8. UNIT or CA AGREEMENT NAME: Big Indian #3	
2. NAME OF OPERATOR: EnCana Oil & Gas (USA) Inc.								9. WELL NAME and NUMBER: Big Indian Fed 14-42-30-25	
3. ADDRESS OF OPERATOR: 370 - 17th St, Suite 170C CITY Denver STATE CO ZIP 80202				PHONE NUMBER: (720) 876-5339				10. FIELD AND POOL, OR WILDCAT, Big Indian (South) Judd	
4. LOCATION OF WELL (FOOTAGES) At SURFACE: 1292' FSL & 1361' FWL At PROPOSED PRODUCING ZONE: 1109' FSL & 1721' FWL								11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 14 30S 25E S	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: Approximately 10 Miles SE of La Sal, UT						12. COUNTY: San Juan		13. STATE: UTAH	
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 1109'			16. NUMBER OF ACRES IN LEASE: 2200.00			17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40			
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 464'			19. PROPOSED DEPTH: 3,217			20. BOND DESCRIPTION: RLB0001191			
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 6682.5 GR			22. APPROXIMATE DATE WORK WILL START: 7/15/2007			23. ESTIMATED DURATION: 20 Days			

24.

SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12 1/4	9 5/8 J-55 36#	783	Class G + 2% gel 250sx 2.09 cuft/sx 12.5#
7 7/8	5 1/2 J-55 17#	3,438	Class G + 2% gel 600sx 1.43 cuft/sx 13#

25.

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

NAME (PLEASE PRINT) **Jevin Croteau**

TITLE Regulatory Analyst

SIGNATURE

DATE 5/2/07

(This space for State use only)

API NUMBER ASSIGNED:

**Approved by the
Utah Division of
Oil, Gas and Mining**

APPROVAI:

RECEIVED

MAY 03 2007

(11/2001)

**Federal Approval of this
Action is Necessary**



(See Instructions on Reverse Side)

Date: 05-07-01

By:

DIV. OF OIL, GAS & MINING

R. 25 E.



SCALE: 1" = 1000'

T. 30 S.

LATITUDE
NORTH 38.174316 DEG.
LONGITUDE
WEST 109.150827 DEG.

NORTHING
557442.42
EASTING
2675269.32

DATUM
SPCS UT SOUTH (NAD 27)

BHL LATITUDE
NORTH 38.173812 DEG.
BHL LONGITUDE
WEST 109.149595 DEG.



SURVEYOR'S STATEMENT

I, Clement R. Williams, of Rock Springs, Wyoming, hereby state: This map was made from notes taken during an actual survey under my direct supervision on APRIL 20, 2007, and it correctly shows the location of BIG INDIAN FED 14-42-30-25.

NOTES

- ◆ WELL LOCATION
- FOUND MONUMENT (BC)
- APPROXIMATE BHL




EXHIBIT 1

DR RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 382-5028

SCALE: 1" = 1000'
JOB No. 15045
REVISED: 4/24/07

**PLAT OF DRILLING LOCATION
FOR
ENCANA OIL & GAS (USA) INC.**

**1292' F/SL & 1361' F/WL, SECTION 14,
T. 30 S., R. 25 E., SALT LAKE B.M.
SAN JUAN COUNTY, UTAH**

Drilling Program

Page 1

ONSHORE OIL & GAS ORDER NO. 1**Approval of Operations on Onshore****Federal and Indian Oil and Gas Leases**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Order No. 1, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

1. FORMATION TOPS

The estimated tops of important geologic markers are as follows:

Formation	Depth (TVD)	Subsea
Burro Canyon	Surface	+6829'
Morrison	733'	+5954'
Entrada	1020'	+5667'
Navajo	1226'	+5461'
Kayenta	1861'	+4826'
Wingate	2098'	+4589'
Chinle/Cutler	Faulted Out	Faulted Out
Honaker Trail	2972'	+3715'
HKTR MKR 5	3147'	+3520'
Total Depth	3217'	+3470'

2. ANTICIPATED DEPTH OF WATER, OIL & GAS

The estimated depths at which the top and bottom of the anticipated water, oil, gas or other mineral bearing formations as expected to be encountered are as follows:

Substance	Formation	Depth (TVD)
Gas	Cutler	2357'
Gas	Honaker Trail	2972'

All fresh water and prospectively valuable minerals encountered during drilling, will be recorded by depth and adequately protected. All indications of usable water (10,000 ppm or less TDS) shall be reported to the Durango Field Office prior to running the next string of casing or before plugging orders are requested, whichever occurs first.

Drilling Program

Page 2

If noticeable water flows are detected, samples will be submitted to the BLM along with any water analyses conducted.

3. BOP EQUIPMENT/REQUIREMENTS

EnCana Oil & Gas (USA), Inc.'s minimum specification for pressure control equipment are as follows:

Ram Type: 11" Hydraulic double ram with annular, 3000 psi w.p.

Ram type preventers and associated equipment shall be tested to approved stack working pressure if isolated by test plug or to 70% of internal yield pressure of casing. Pressure shall be maintained for at least 10 minutes or until requirements of test are met, whichever is longer. If a test plug is utilized, no bleed-off pressure is acceptable. For a test not utilizing a test plug, if a decline in pressure of more than 10% in 30 minutes occurs, the test shall be considered to have failed. Valve on casing head below test plug shall be open during test of BOP stack.

Annular type preventers (if used) shall be tested to 50% of rated working pressure. Pressure shall be maintained at least 10 minutes or until provisions of test are met, whichever is longer.

As a minimum, the above test shall be performed:

- a. when initially installed:
- b. whenever any seal subject to test pressure is broken
- c. following related repairs: and
- d. at 30 day intervals

Valves shall be tested from working pressure side during BOPE tests with all down stream valves open.

When testing the kill line valve(s) shall be held open or the ball removed.

Annular preventers (if used) shall be functionally operated at least weekly.

Pipe and blind rams shall be activated each trip, however, this function need not be performed more than once a day.

A BOPE pit level drill shall be conducted weekly for each drilling crew.

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests. Pressure tests shall apply to all related well control equipment.

BOP systems shall be consistent with API RP53. Pressure tests will be conducted before drilling out from under casing strings which have been set and cemented in place. Blowout preventer controls will be installed prior to drilling the surface casing plug and will remain in use until the well is completed or abandoned. Preventers will be inspected and operated at least daily to ensure good mechanical working order, and this inspection will be recorded on

Drilling Program

Page 3

the daily drilling report. Preventers will be pressure tested before drilling casing cement plugs.

The BLM in Moab, Utah shall be notified, at least 24 hours prior to initiating the pressure test, in order to have a BLM representative on location during pressure testing.

- a. The size and rating of the BOP stack is shown on the attached diagram.
- b. A choke line and a kill line are to be properly installed. The kill line is not to be used as a fill-up line.
- c. The accumulator system shall have a pressure capacity to provide for repeated operation of hydraulic preventers.
- d. Drill string safety valve(s), to fit all tools in the drill string, are to be maintained on the rig floor while drilling operations are in progress.

4. CASING AND CEMENTING PROGRAMS

- a. The BLM in Moab, Utah shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.
- b. The proposed casing and cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals. Any isolating medium other than cement shall receive approval prior to use. The casing setting depth shall be calculated to position the casing seat opposite a competent formation which will contain the maximum pressure to which it will be exposed during normal drilling operations. Determination of casing setting depth shall be based on all relevant factors, including; presence/absence of hydrocarbons; fracture gradients; usable water zones; formation pressures; lost circulation zones; other minerals; or other unusual characteristics. All indications of usable water shall be reported.
- c. Casing design shall assume formation pressure gradients of 0.44 to 0.50 psi per foot for exploratory wells (lacking better data).
- d. Casing design shall assume fracture gradients from 0.70 to 1.00 psi per foot for exploratory wells (lacking better data).
- e. Casing collars shall have a minimum clearance of 0.422 inches of all sides in the hole/casing annulus, with recognition that variances can be granted for justified exceptions.
- f. All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.
- g. All casing except the conductor casing, shall be new or reconditioned and tested used casing that meets or exceeds API standards for new casing.
- h. The surface casing shall be cemented back to surface either during the primary cement job or by remedial cementing.
- i. All indication of usable water shall be reported to the authorized officer prior to running the

Drilling Program

Page 4

next string of casing or before plugging orders are requested, whichever occurs first.

- j. Surface casing shall have centralizers on the bottom 3 joints of casing (a minimum of one centralizer per joint starting with the shoe joint).
- k. Top plugs shall be used to reduce contamination of cement by displacement fluid. A bottom plug or other acceptable technique, such as a suitable preflush fluid, inner string cement method, etc. shall be utilized to help isolate the cement from contamination by the mud fluid being displaced ahead of the cement slurry.
- l. All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string length or 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective actions shall be taken.
- m. On all exploratory wells, and on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
- n. The proposed casing program will be as follows:

Purpose	Depth (MD)	Hole Size	O.D.	Weight	Grade	Type	New/Used
Surface	0'-783'	12 1/4"	9-5/8"	36#	J-55	ST&C	New
Production	0'-3438'	7-7/8"	5-1/2"	17#	J-55	LT&C	New

- o. Casing design subject to revision based on geologic conditions encountered.
- p. The cement program will be as follows:

Surface	Type and Amount
0-783'	Lead: 150 sx Class G 50/50 Poz + 2% gel, 2.09 cuft/sx yield, 12.5 ppg Tail: 100 sx Class G, 1.15 cuft/sx yield, 15.8 ppg
Production	Type and Amount
783'-3438'	600 sx Class G 50/50 Poz, 1.43 cuft/sx yield, 13 ppg

- q. The BLM in Moab, Utah should be notified, with sufficient lead time, in order to have a BLM representative on location while running all casing strings and cementing.
- r. After cementing but before commencing any test, the casing string shall stand cemented until the cement has reached a compressive strength of at least 500 psi at the shoe. WOC time shall be recorded in the driller's log.
- s. The following reports shall be filed with the District Manager within 30 days after the work is

Drilling Program

Page 5

completed.

1. Progress reports, Form 3160-5, "Sundry Notices and Reports on Wells", must include complete information concerning:

- i. Setting of each string of casing, showing the size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
- ii. Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.

- t. Auxiliary equipment to be used is as follows:

1. Kelly cock
2. No bit float is deemed necessary.
3. A sub with a full opening valve.

5. MUD PROGRAM

- a. The proposed circulating mediums to be employed in drilling are as follows:

Interval (MD)	Mud Type	Mud Wt.	Visc.	F/L
0-2010'	Water	+/- 8.5	+/- 28	N.C.
2010'-TD	LSND	+/- 8.5-9.0	+/- 55-60	+/- 8

- b. Mud monitoring equipment to be used is as follows: Periodic checks of the mud system will be made each tour. The mud level will be checked visually.

1. There will be sufficient mud on location to ensure well control.
2. A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, static filtration loss and Ph.

- c. Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing or completion operations.

6. EVALUATION PROGRAM – TESTING, LOGGING AND CORING

The anticipated type and amount of testing, logging and coring are as follows:

- a. No drill stem tests are anticipated, however, if DST's are run, the following requirements will be adhered to:

Initial opening of drill stem test tools shall be restricted to daylight hours unless specific approval to start during other hours is obtained from the authorized officer. However, DST's may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e. lighting which is adequate for visibility and vapor-proof for safe operations). Packers can be released, but tripping shall not

Drilling Program

Page 6

begin before daylight, unless prior approval is obtained from the authorized officer. Closed chamber DST's may be accomplished day or night.

A DST that flows to the surface with evidence of hydrocarbons shall be reversed out of the testing string under controlled surface conditions. This would involve providing some means for reverse circulation.

Separation equipment required for the anticipated recovery shall be properly installed before a test starts.

All engines within 100 feet of the wellbore that are required to "run" during the test shall have spark arresters or water cooled exhausts.

- b. The logging program will consist of a DIL/CNL/LDT/GR/SP from TD to base of the surface casing.
- c. No whole cores are anticipated. Depending upon evaluation of the open hole logs, several sidewall cores may be obtained in formations of interest.
- d. Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, work over, and/or completions, will be filed with form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the authorized officer (AO).
- e. The anticipated completion program is as follows:
Perforate zones of interest, fracture stimulate as necessary and place on production.

7. ABNORMAL PRESSURES AND H2S GAS

- a. The maximum expected bottom hole pressure is 1100 psi (pressure gradient of 0.33 psi/ft). Source of pressure estimate was from data obtained for the Honaker Trail geological formation via pressures obtained in the Big Indian Unit #3 and #4 wells (#4 well is located within 1 mile of the proposed location).
- b. No hydrogen sulfide gas is anticipated, no abnormal pressures or temperatures are anticipated.
- c. As per Onshore Order No. 6, III.A.2.b., if hydrogen sulfide is present the "operator shall initially test the H2S concentration of the gas stream for each well or production facility ..." Submit the results of this test within 30 days of filing Form 3160-4, "Well Completion or Recompletion Report and Log".

8. OTHER INFORMATION AND NOTIFICATION REQUIREMENTS

- a. The BLM in Moab (435-259-2100) shall be notified at least 24 hours prior to:
 - 1. Spudding the well
 - 2. Running the casing strings and cementing

Drilling Program

Page 7

3. BOP tests/casing pressured tests.

- b. Within 30 days of completion of the well as a dry hole or producer, a copy of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, work over, and/or completions operations will be filed with a Completion Report (Form 3160-4), in triplicate. Submit casing/cementing reports and other subsequent reports via Sundry Notice Form 3160-5.
- c. In accordance with 43 CFR 3162.4-3, this well shall be reported on MMS Form 3160, "Monthly Report of Operations", starting with the month in which drilling operations commence, and continuing each month until the well is physically plugged and abandoned.
- d. The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or the date on which gas is first measured through permanent metering facilities, whichever first occurs.
- e. Pursuant to NTL-4A, lessees or operators are authorized to vent/flare gas during the initial well evaluation tests, not exceeding a period of 30 days or the production of 50 MMCF of gas, whichever occurs first. An application must be filed with the District Engineer and approval received, for any venting/flaring of gas beyond the initial 30 day authorized period.
- f. A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9.d), shall be submitted to the appropriate District Office within 60 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b.4).
- g. Off-lease measurement and commingling of production must be approved by the authorized officer.
- h. Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43

Drilling Program

Page 8

CFR 3162.4-1(b)(5)(ii).

- i. The BLM in Moab (435-259-2100) shall be notified within 5 business days of production start-up if either of the following two conditions occur:

1. The well is placed on production, or
2. The well resumes production after being off of production for more than 90 days.

"Placed on production" means shipment or sales of hydrocarbons from temporary tanks, production into permanent facilities or measurement through permanent facilities. Notification may be written or verbal with written follow-up within 15 days.

- j. Drilling is planned to commence upon approval. Completion will begin approximately 30 days after drilling is completed.
- k. It is anticipated that the drilling of this well will take approximately 10-15 days.
- l. No location will be constructed or moved, no well will be plugged, and no drilling or work over equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.
- m. Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.
- n. If a replacement rig is contemplated for completion operations, a "Sundry Notice" Form 3160-5 to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.
- o. Pursuant to Onshore Order No. 7, with the approval of the District Engineer, produced water may be temporarily disposed of into unlined pits for a period of up to 90 days. During the period so authorized, an application for approval of the permanent disposal method, along with the required water analysis and other information, must be submitted to the District Engineer.

If underground injection is proposed, an EPA or State UIC permit shall also be required and submitted to this office.

- p. No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5 will be filed with the AO within 30 days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.
- q. As per 43 CFR 3162.6, each drilling producing or abandoned well shall be identified with the operator's name, the lease serial number, the well number, and the surveyed description of the well (either footages or the quarter-quarter section, the section, township and range). The Indian lessor's name may also be required. All markings shall

ONSHORE ORDER No. 1

EnCana Oil & Gas (USA), Inc.

Big Indian Federal 14-42-30-25

1292' FSL & 1361' FWL (surface)

Section 14-T30S-R25E

1109' FSL & 1721' FWL (bottom hole)

Section 14-T30S-R25E

San Juan County, Utah

Lease No. UTU-89097

Drilling Program

Page 9

be legible and in a conspicuous place.

r. Bureau of Land Management, Moab Field Office Address and Contacts:

Address: 82 East Dogwood Ave. Phone: 435-259-2100

Moab, Utah 84532

Business Hours: 7:45 a.m. to 4:30 p.m. (Mountain Time), Mon-Fri.

After Hours:


Eric Jones	Petroleum Engineer	435-259-2117
------------	--------------------	--------------

3M ANNULAR


3M DOUBLE RAM BOP

3" CHOKE LINE FROM
OUTLET ON BOTTOM
SIDE OF RAMS

2" KILL LINE



ENCANA




ENCANA OIL & GAS (USA) INC

Location: UTAH Slot: Slot #1 Big Indian Fed 14-42-30-25
 Field: SAN JUAN COUNTY (True) Well: Big Indian Fed 14-42-30-25
 Facility: SEC.14-T30S-R25E Wellbore: Big Indian Fed 14-42-30-25 PWB

**BAKER
HUGHES**
INTEQ

Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	20.00	0.000	79.622	20.00	0.00	0.00	0.00	0.00
End of Tangent	200.00	0.000	79.622	200.00	0.00	0.00	0.00	0.00
Build (S)	683.97	29.038	79.622	663.52	21.62	118.08	6.00	94.89
End of Tangent (S)	1563.08	29.038	79.622	1432.11	98.49	537.81	0.00	432.19
3D Arc (S) (Casing Pt)	2339.62	19.168	230.072	2180.00	47.80	630.60	6.00	537.90
3D Arc (Top Res)	2527.01	19.162	230.070	2357.00	8.31	583.42	0.00	514.18
3D Arc (BHL / well td)	3437.48	19.171	230.078	3217.00	-183.54	354.19	0.00	398.92





Planned Wellpath Report

Big Indian Fed 14-42-30-25 PWP

Page 1 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION

Operator	ENCANA OIL & GAS (USA) INC	Slot	Slot #1 Big Indian Fed 14-42-30-25
Area	UTAH	Well	Big Indian Fed 14-42-30-25
Field	SAN JUAN COUNTY (True)	Wellbore	Big Indian Fed 14-42-30-25 PWB
Facility	SEC.14-T30S-R25E		

REPORT SETUP INFORMATION

Projection System	NAD27 / Lambert Utah State Planes, Southern Zone (4303), US feet	Software System	WellArchitect™ 1.2
North Reference	True	User	L. Doubek
Scale	0.999974	Report Generated	04/19/07 at 13:43:55
Wellbore last revised	04/19/07	Database/Source file	WA_Denver/Big_Indian

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North [feet]	East [feet]	Easting [US feet]	Northing [US feet]	Latitude [°]	Longitude [°]
Slot Location	0.00	0.00	2675269.45	557442.55	38 10 27.538N	109 09 02.977W
Facility Reference Pt			2675269.45	557442.55	38 10 27.538N	109 09 02.977W
Field Reference Pt			2674299.58	558893.86	38 10 42.121N	109 09 14.663W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Slot #1 Big Indian Fed 14-21-30-25 (RT) to Facility Vertical Datum	6659.70 feet
Horizontal Reference Pt	Slot	Rig on Slot #1 Big Indian Fed 14-21-30-25 (RT) to Mean Sea Level	6659.70 feet
Vertical Reference Pt	Rig on Slot #1 Big Indian Fed 14-21-30-25 (RT)	Facility Vertical Datum to Mud Line (Facility)	0.00 feet
MD Reference Pt	Rig on Slot #1 Big Indian Fed 14-21-30-25 (RT)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	117.39°



Planned Wellpath Report

Big Indian Fed 14-42-30-25 PWP

Page 2 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION			
Operator	ENCANA OIL & GAS (USA) INC	Slot	Slot #1 Big Indian Fed 14-42-30-25
Area	UTAH	Well	Big Indian Fed 14-42-30-25
Field	SAN JUAN COUNTY (True)	Wellbore	Big Indian Fed 14-42-30-25 PWB
Facility	SEC.14-T30S-R25E		

WELLPATH DATA (42 stations) † = interpolated/extrapolated station							
MD [feet]	Inclination [°]	Azimuth [°]	TVD [feet]	Vert Sect [feet]	North [feet]	East [feet]	DLS [°/100ft]
0.00†	0.000	79.622	0.00	0.00	0.00	0.00	0.00
20.00	0.000	79.622	20.00	0.00	0.00	0.00	0.00
120.00†	0.000	0.000	120.00	0.00	0.00	0.00	0.00
200.00	0.000	79.622	200.00	0.00	0.00	0.00	0.00
220.00†	1.200	79.622	220.00	0.17	0.04	0.21	6.00
320.00†	7.200	79.622	319.68	5.95	1.36	7.41	6.00
420.00†	13.200	79.622	418.06	19.94	4.55	24.82	6.00
520.00†	19.200	79.622	514.04	41.99	9.57	52.25	6.00
620.00†	25.200	79.622	606.59	71.84	16.37	89.40	6.00
683.97	29.038	79.622	663.52	94.89	21.62	118.08	6.00
720.00†	29.038	79.622	695.02	108.71	24.77	135.28	0.00
820.00†	29.038	79.622	782.45	147.08	33.52	183.02	0.00
920.00†	29.038	79.622	869.88	185.45	42.26	230.77	0.00
1020.00†	29.038	79.622	957.31	223.82	51.01	278.51	0.00
1120.00†	29.038	79.622	1044.73	262.19	59.75	326.26	0.00
1220.00†	29.038	79.622	1132.16	300.56	68.49	374.00	0.00
1320.00†	29.038	79.622	1219.59	338.92	77.24	421.75	0.00
1420.00†	29.038	79.622	1307.02	377.29	85.98	469.50	0.00
1520.00†	29.038	79.622	1394.45	415.66	94.73	517.24	0.00
1563.08	29.038	79.622	1432.11	432.19	98.49	537.81	0.00
1620.00†	25.719	81.376	1482.65	453.11	102.84	563.62	6.00
1720.00†	19.961	85.754	1574.78	485.22	107.36	602.13	6.00
1820.00†	14.391	93.413	1670.30	511.13	107.88	631.58	6.00
1920.00†	9.354	109.671	1768.15	530.55	104.40	651.66	6.00
2020.00†	6.292	149.084	1867.28	543.28	96.96	662.13	6.00
2120.00†	7.963	197.235	1966.58	549.17	85.63	662.90	6.00
2220.00†	12.607	219.200	2064.99	548.16	70.55	653.94	6.00
2320.00†	18.061	228.821	2161.41	540.26	51.87	635.36	6.00
2339.62	19.168	230.072	2180.00 ¹	537.90	47.80	630.60	6.00
2420.00†	19.166	230.071	2255.92	527.73	30.86	610.36	0.00
2520.00†	19.163	230.070	2350.38	515.07	9.79	585.19	0.00
2527.01	19.162	230.070	2357.00 ²	514.18	8.31	583.42	0.00
2620.00†	19.163	230.071	2444.84	502.41	-11.28	560.02	0.00
2720.00†	19.164	230.072	2539.30	489.76	-32.35	534.84	0.00
2820.00†	19.165	230.073	2633.76	477.10	-53.42	509.67	0.00
2920.00†	19.166	230.074	2728.21	464.44	-74.49	484.49	0.00
3020.00†	19.167	230.074	2822.67	451.78	-95.56	459.31	0.00
3120.00†	19.168	230.075	2917.13	439.12	-116.63	434.14	0.00
3220.00†	19.169	230.076	3011.58	426.46	-137.71	408.95	0.00
3320.00†	19.170	230.077	3106.04	413.79	-158.78	383.77	0.00



Planned Wellpath Report

Big Indian Fed 14-42-30-25 PWP

Page 3 of 3



INTEQ

REFERENCE WELLPATH IDENTIFICATION			
Operator	ENCANA OIL & GAS (USA) INC	Slot	Slot #1 Big Indian Fed 14-42-30-25
Area	UTAH	Well	Big Indian Fed 14-42-30-25
Field	SAN JUAN COUNTY (True)	Wellbore	Big Indian Fed 14-42-30-25 PWB
Facility	SEC.14-T30S-R25E		

WELLPATH DATA (42 stations) † = interpolated/extrapolated station							
MD [feet]	Inclination [°]	Azimuth [°]	TVD [feet]	Vert Sect [feet]	North [feet]	East [feet]	DLS [°/100ft]
3420.00†	19.171	230.078	3200.49	401.13	-179.85	358.59	0.00
3437.48	19.171	230.078	3217.00 ³	398.92	-183.54	354.19	0.00

TARGETS									
Name	MD [feet]	TVD [feet]	North [feet]	East [feet]	Grid East [us survey feet]	Grid North [us survey feet]	Latitude [°]	Longitude [°]	Shape
1) Big Indian Fed 14-42-30-25 CSG	2339.62	2180.00	47.80	630.60	2675898.63	557506.17	38 10 28.010N	109 08 55.081W	point
2) Big Indian Fed 14-42-30-25 Top Reservoir	2527.01	2357.00	8.31	583.42	2675852.46	557465.51	38 10 27.620N	109 08 55.671W	circle
3) Big Indian Fed 14-42-30-25 BHL Target	3437.48	3217.00	-183.54	354.19	2675628.12	557267.97	38 10 25.723N	109 08 58.542W	circle

SURVEY PROGRAM				
Ref Wellbore: Big Indian Fed 14-42-30-25 PWB		Ref Wellpath: Big Indian Fed 14-42-30-25 PWP		
Start MD [feet]	End MD [feet]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	3437.48	MTC (Collar, pre-2000) (Standard)		Big Indian Fed 14-42-30-25 PWB

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

ONSHORE OIL & GAS ORDER NO. 1

Thirteen Point Surface Use Plan

The onsite inspection for the subject location was conducted on March 21, 2007. In attendance at the onsite inspection were the following individuals:

<u>Name</u>	<u>Position</u>	<u>Organization</u>
Rich McClure	Natural Resource Specialist	Bureau of Land Management
Ron Krist	Construction Supervisor	EnCana Oil & Gas (USA) Inc.
Jevin Croteau	Regulatory Analyst	EnCana
Ron Rennke	Surveyor	D.R. Griffin & Assoc.
Carol S. DeFrancia	Archaeologist	4-Corners Archaeological Svs.
Mike Shumway	Construction	K-SUE Corporation
Chuck Zimmerman	Construction	K-SUE
Ward Priestley	Construction	Williams Construction
George Sanders	Construction	Ebberts Construction

1. EXISTING ROADS

- a. The proposed well site is located on the existing Big Indian #4 well pad located approximately 10 miles Southeast of La Sal, Utah.
- b. Directions from La Sal, Utah are as follows:

From La Sal travel State Highway 46 westerly for 2.3 miles. Turn left on Lisbon (113) Road travel south southeasterly for approximately 5.7 miles to the 370 Road. Stay to the left and travel southeasterly for 6.1 miles to an existing road. Turn left travel northeasterly then southeasterly for 2.4 miles to the existing Big Indian #4 location.
- c. Existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well as per the road use agreement.
- d. Dust control measures will be implemented during dry weather when necessary. These may include mag chloride or other palliative.

2. PLANNED ACCESS ROADS

- a. For access roads, refer to Topo Maps A and B.
- b. Some Improvements to the existing access road may be necessary.
- c. No turnouts will be necessary.
- d. All surface materials needed for construction will be procured from a commercial source, except those materials that will be generated during the construction of this well (excess fill, etc.).
- e. The roads shall be maintained reasonably smooth, and free of ruts, soft spots, chuckholes, rocks, slides and washboards. The BLM "Gold" book shall be followed for specifications on road design and culvert installation. All weather surfacing will be

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

required if the well becomes a producer. A regular maintenance program shall include blading, ditching, sign replacement, surfacing, and culvert maintenance. All vehicles servicing the well are restricted to use of the approved access road and well pad.

- f. No new Culverts or low water crossings will be necessary unless specified by the BLM.
- g. No fence cuts or cattle guards will be necessary unless specified by the BLM.
- h. A road and pipeline right-of-way will not be required from the BLM. Both the access road and pipeline will be on lease and entirely within the Big Indian #3 Unit. See the attached Topo Map B.
- i. Surface disturbance and vehicle travel will be limited to the approved location and approved pipeline/access road route. Any additional area needed will be approved by the BLM in advance.
- j. No surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. EnCana will adhere to the conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.
- k. If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of-way grant, the prior on-lease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.
- l. If at any time the facilities located on public lands authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change) the BLM will process a change in authorization to the appropriate statute. The authorization will be subject to appropriate rental or other financial obligations determined by the BLM.
- m. If the well is productive, the access road will be rehabilitated or brought to Resource (Class III) Road Standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Filed Office Manager will be notified so that temporary drainage control can be installed along the access road.
- n. All brush, limbs, and other woody material will be stockpiled separately from the topsoil along the roadway, or near the well pad. If any topsoil can be salvaged it will be stockpiled near the well pad for future reclamation. If the soil stockpile is not used within six months it will be seeded to ensure topsoil integrity and prevent erosion.
- o. No pullouts or off-road parking will be allowed unless specifically authorized. "Keep vehicles on road surface" signs will be installed to assist with compliance. Shortcutting by vehicles operated by EnCana or its contractors, on roads not identified as access routes in the APD, will not be allowed.

3. LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS OF THE PROPOSED

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

LOCATION. SEE TOPO MAP A.

- a. Water Wells - 0
- b. Injection or Disposal Wells - 0
- c. Producing Wells - 2
- d. Drilling Wells - 0
- e. Shut In Wells - 1
- f. Plugged and Abandoned Wells - 0

4. LOCATION OF PRODUCTION FACILITIES

- a. If the well is productive all production facilities will be located on the well pad. The proposed facilities to be located on the well pad will be a typical tank battery, which include a separator, meter building (with tube and meter), two 400 Hundred bbl tanks and if needed one 500 gal tank and methanol pump or deh'y equipment.
- b. All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the BLM - Moab Field Office.
- c. The proposed gas gathering line will be buried from the well head to the battery site then tied into the existing pipeline on location.
- d. All permanent structures (onsite for six months or longer) constructed or installed will be painted a flat, non-reflective earth tone color which will match the adjacent vegetation. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded. The actual color will be Juniper Green as specified by the Bureau of Land Management.
- e. All site security guidelines identified in 43 CFR 3162.7-5 and specified in Onshore Order No. 3 shall be adhered to.
- f. The oil and gas measurement facilities will be installed on the well location. The gas flowline will be buried from the wellhead to the meter and tied into the existing pipeline. Meter runs will be housed. Oil and gas meters will be calibrated prior to first sales and quarterly thereafter. A copy of the meter calibration reports will be submitted to the BLM - Moab Field Office. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7, Onshore Oil and Gas Order No. 5 and the American Gas Association (AGA) Report No. 3.
- g. If a tank battery is constructed on this lease, it will be surrounded by a berm of sufficient capacity to contain 1 ½ times the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All oil production and measurement shall conform to the provisions of 43 CFR 3162.7 and Onshore Oil and Gas Order No. 4.
- h. Production facilities on location may include a lined or unlined produced water pit as specified in Onshore Oil and Gas Order No. 7. If water is produced from the well, an application in conformance with Order No. 7 must be submitted.

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

5. LOCATION AND TYPE OF WATER SUPPLY

- a. The source of water for drilling and completion purposes will be obtained from the La Sal Creek located in the SW/4 of Section 8, T28S R25E, San Juan County, Utah.
- b. This water source will be permitted under the State of Utah, Department of Natural Resources, Division of Water Rights. Water Right Number 05-6.
- c. Water will be hauled to the location over the proposed access roads outlined in the SUP.

6. CONSTRUCTION MATERIALS

- a. All materials needed for construction will be procured from a commercial source, except those materials that will be generated during the construction of this well (excess fill, etc.).
- b. The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.
- c. No gravel or other related minerals from new or existing pits on Federal land will be used in the construction of roads, well pads, etc., without prior approval from the BLM.

7. METHODS FOR HANDLING WASTE DISPOSAL

- a. Drill cuttings are to be contained and buried in the reserve pit.
- b. The reserve pit will be sealed in such a manner as to prevent leakage of the fluids. Methods available to insure containment of drilling fluids in the reserve pit include lining the inside of the pit with at least a 30 mil plastic liner. If a plastic liner is used, the bottom of the pit shall be smooth and free of any sharp rocks. If the pit has a rocky bottom, it shall be bedded with a material such as soil, sand, straw or hay to avoid the possibility of puncturing the liner. A minimum of not less than a 2 foot freeboard will be maintained in the pit at all times. All oil or floating debris will be removed from the pit immediately after the drilling and after the stimulation phase of the well.
- c. The reserve pit will be located on the NW corner of the disturbed pad, and the pit walls will be sloped at no greater than 1 1/2 to 1.
- d. The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed and shall remain until the pit is dry. As soon as the reserve pit has dried, all areas not needed for production will be rehabilitated.
- e. Garbage is to be contained in the trash cage. The trash cage will be totally enclosed with small mesh wire to prevent wind scattering and wildlife entry. All garbage will be hauled to an approved disposal site at the end of drilling/completion operations.
- f. Sewage will be disposed of in accordance with State and County regulations. No sewage boreholes will be allowed. Chemical porta-toilets will be furnished and their contents hauled to an approved disposal site.
- g. The produced fluids (produced water, frac fluid and possibly condensate), while testing the well will be flowed back to a 400 bbl test tank. Any condensate will be skimmed and

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

transferred to production tanks. Sand and produced fluids other than condensate will be transferred to the reserve pit until such time as the well is cleaned up sufficiently to produce pipeline quality gas. Any spills of oil, gas, salt water or other produced fluids will be cleaned up and removed.

8. ANCILLARY FACILITIES

No camps, airstrips or other facilities will be necessary.

9. WELLSITE LAYOUT

- a. The survey plats are attached.
- b. The well pad plan is attached with the location of the reserve pit and access road onto the well pad.
- c. A cross section of the well pad with the cut and fill diagram is attached.
- d. All wells, whether drilling, producing, suspended, or abandoned, will be identified in accordance with 43 CFR 3162.6.
- e. The reserve pit will be designed to prevent the collection of surface runoff.
- f. The reserve pit liner shall remain intact until the reserve pit is reclaimed. Flare pits must be located a sufficient distance from the reserve pit to prevent the liner from being damaged during flaring operations.
- g. Prior to rigging up, a one-foot high berm will be constructed around the perimeter of the well pad to contain all storm events/spills from going downstream of the well pad. A lined sump pit may be utilized to contain the fluids. The need for the berm will be reassessed upon completion of the well and after production is established.
- h. Compaction and construction of the berms surrounding the tank or tank batteries will be designed to prevent lateral movement of fluids through the berm, prior to any storage of fluids. All load lines and valves shall be placed inside the bermed areas.
- i. There shall be a sign or marker on location with the name of the operator, lease serial number, well number, and legal location of the well.

10. PLANS FOR RECLAMATION OF THE SURFACE

The following surface reclamation will be done upon completion of the drilling operations.

- a. Where topsoil material is available it will be removed from the location, saved and stockpiled separately on the edge of the pad to be used for reclamation purposes.
- b. Topsoil along the access road will be reserved in place adjacent to the road.
- c. Immediately upon completion of drilling, all equipment that is not necessary for production shall be removed.
- d. When the reserve pit has completely dried the reserve pit, existing pit and that portion of the location not needed for production will be reclaimed.
- e. All road surfacing will be removed prior to the rehabilitation of roads.
- f. Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

use.

- g. All disturbed areas will be recontoured to replicate the natural slope.
- h. The stockpiled topsoil will be evenly distributed over the disturbed area where available.
- i. Prior to reseeding, all disturbed areas, including the access roads will be scarified and left with a rough surface.
- j. Seed will be broadcast or drilled between September and October, or at a time specified by the BLM. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.
- k. The following seed mixture or one approved by the BLM will be used. Seed labels from each bag shall be available for inspection while seeding is being accomplished. In the event grasses and native vegetation is not established after the first seeding application, subsequent applications will be performed until grasses and/or native vegetation is established.

<u>Common Name</u>	<u>Pure Live Seed (PLS) lbs /acre</u>
Indian ricegrass	4.0
Crested wheatgrass	4.0
Four-wing saltbush	4.0
Alfalfa	0.5
	12.5 lbs/acre

- l. The abandonment marker will be one of the following, as specified by the BLM:
 - 1) at least four feet above ground level,
 - 2) at restored ground level, or
 - 3) below ground level.

In any case the marker shall be inscribed with the following: operator name, lease number, well name and surveyed description (township, range, section and either quarter-quarter or footages).

- m. Vegetation or soil disturbance by the operator will be held to the minimum consistent with practical construction operations and the operator will smooth all disturbed areas to conform as nearly as practical to the adjacent terrain.
- n. To the degree it is feasible, natural drainage will not be altered.
- o. Reclamation will be considered successful when the desired vegetative species are established, erosion is controlled, weeds are considered a minimal threat, and it is likely that ground cover will return to a desirable condition. EnCana will continue revegetation efforts until this standard is met. BLM shall be responsible for determining when reclamation efforts are successful.
- p. A fence shall be installed around the perimeter of the area undergoing reclamation. The fence shall be maintained in a manner to prevent cattle from entering the area, and shall be constructed as follows: Posts to be no more than 16' apart; fence wire: four wires of

ONSHORE ORDER No. 10
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

at least 12.5 gauge, double strand twisted; two stays between posts; wire stretched taut between brace panels, wire spacing from the ground up: 14", 22", 30", 42". Fence shall be maintained in place for a minimum of 3 years, and will be removed by EnCana when so instructed by the BLM.

11. SURFACE OWNERSHIP

Well site - Bureau of Land Management

Roads - All access roads are located or maintained by the State and County Road Departments or are on lands managed by the Bureau of Land Management.

12. OTHER INFORMATION

- a. A Class III archeological survey has been conducted by 4 Corners Archaeological Services for the surface location, access road and pipeline right-of-way and will be sent under separate cover.
- b. The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work that might further disturb such materials, and contact the BLM Field Office. Within five (5) working days, the BLM will inform the operator as to:
 - Whether the materials appear eligible for the National Register of Historic Places;
 - The mitigation measures the will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
 - A time frame for the BLM to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the BLM are correct and that mitigation is appropriate.

If the operator wishes, at the time, to relocate activities to avoid the expenses of mitigation and/or the delays associated with this process, the BLM will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The BLM will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the BLM that the required mitigation has been completed, the operator will then be allowed to resume construction.

- c. The BLM would conduct U.S. Fish and Wildlife Service (USFWS) consultation and coordination as necessary for all mitigation activities relating to T&E, candidate species and their habitats. In areas that have not been previously surveyed or cleared for these species, a qualified biologist/botanist would conduct surveys for these species in areas of potential habitat prior to disturbance. If T&E, candidate, or sensitive species are found, consultation with the USFWS would be initiated, as necessary, and construction activities would be curtailed until the BLM, USFWS, and Operators concur on which activities can be authorized.
- d. The BLM, Moab Field Office will be contacted no earlier than 15 days and no later than

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah

Surface Use Plan

Lease No. UTU-89097

three (3) working days prior to commencement of construction activities.

- e. "Sundry Notice and Report of Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION

Permit Matters

EnCana Oil & Gas (USA) INC.
370 17TH Street, Suite 1700
Denver, CO 80202
Jevin Croteau
Office: (720) 876-5339
Cell: (720) 273-6427

Drilling & Completion Matters

EnCana Oil & Gas (USA) INC.
370 17th Street, Suite 1700
Denver, CO 80202
Kevin Brakovec – Drilling Engineer
Office: (720) 876-3668
Cell: (303) 710-0983

ONSHORE ORDER No. 1
EnCana Oil & Gas (USA) Inc.
Big Indian Fed 14-42-30-25
SESW Section 14, T30S-R25E
1292' FSL & 1361' FWL
San Juan County, Utah


Surface Use Plan

Lease No. UTU-89097

CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by EnCana Oil & Gas (USA) Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.



Jevin Croteau

Regulatory Analyst

Date: 5/2/07



ION M. HUNTSMAN, JR.
Governor
GARY R. HERBERT
Lieutenant Governor

State of Utah
DEPARTMENT OF NATURAL RESOURCES
Division of Water Rights

MICHAEL R. STYLER
Executive Director
JERRY D. OLDS
State Engineer/Division Director

ORDER OF THE STATE ENGINEER

For Temporary Change Application Number 05-6 (t31522)

Temporary Change Application Number 05-6 (t31522) in the name of Charles Hardison Redd was filed on May 1, 2006, to change the point of diversion, place of use, and nature of use of 20.00 acre-feet of water as evidenced by Water Right Number 05-6. Heretofore, the water has been diverted from a surface source located North 3420 feet and West 2851 feet from the SE Corner of Section 7, T28S, R25E, SLB&M. The water has been used for the irrigation of 5.00 acres from April 1 to October 31. The water was used in all or portion(s) of Section 35, T28S, R25E, SLB&M; Section 2, T29S, R24E, SLB&M; and Section 11, T29S, R24E, SLB&M.

Hereafter, it is proposed to divert 20.00 acre-feet of water from a surface source located North 712 feet and East 627 feet from the SW Corner of Section 8, T28S, R25E, SLB&M. The nature of use of the water is being changed. The water will now be used for drilling work for oil and gas wells, road construction, and maintenance. The place of use of the water is being changed to all or parts of Section 02, 08, 11, 14, 27, T29S, R24E, SLB&M; Section 08, T29S, R26E, SLB&M; Section 04, 09, 10, 14, 15, T30S, 25E, SLB&M.

Notice of this temporary change application was not published in a newspaper. It is the opinion of the State Engineer that it meets the criteria of Section 73-3-3 of the Utah Code for the approval of temporary change applications.

It is the opinion of the State Engineer that this change application can be approved without adversely affecting existing rights. The applicant is put on notice that diligence must be shown in pursuing the development of this application which can be demonstrated by the completion of the project as proposed in the change application.

It is, therefore, **ORDERED** and Temporary Change Application Number 05-6 (t31522) is hereby **APPROVED** subject to prior rights.

This temporary change application shall expire one year from the date hereof.

It is the applicant's responsibility to maintain a current address with this office and to update ownership of their water right. Please notify this office immediately of any change of address or for assistance in updating ownership.

The applicant is advised to contact the Stream Alteration Section of the Division of Water Rights to ascertain if a Stream Alteration permit is required for this Temporary Change Application.

Your contact with this office, should you need it, is with the Southeastern Regional Office. The telephone number is 435-637-1303.

ORDER OF THE STATE ENGINEER
Temporary Change Application Number
05-6 (131522)
Page 2

This Order is subject to the provisions of Administrative Rule R655-6-17 of the Division of Water Rights and to Sections 63-46b-13 and 73-3-14 of the Utah Code which provide for filing either a Request for Reconsideration with the State Engineer or an appeal with the appropriate District Court. A Request for Reconsideration must be filed with the State Engineer within 20 days of the date of this Order. However, a Request for Reconsideration is not a prerequisite to filing a court appeal. A court appeal must be filed within 30 days after the date of this Order, or if a Request for Reconsideration has been filed, within 30 days after the date the Request for Reconsideration is denied. A Request for Reconsideration is considered denied when no action is taken 20 days after the Request is filed.

Dated this 31 day of May, 2006.




Marc K. Stilson, P.E., Regional Engineer

Mailed a copy of the foregoing Order this 31 day of May, 2006 to:

Charles Hardison Redd
P.O.Box 247
La Sal UT 84530

Stream Alteration Section
Division of Water Rights



DRG RIFFIN & ASSOCIATES, INC.

**ENCANA OIL & GAS (USA) INC.
 BIG INDIAN FED 14-42-30-25**


1414 ELK ST., SUITE 202
 ROCK SPRINGS, WY 82901
 (307) 362-5028

JOB No. 15045

REVISED: 4/25/07

SCALE: 1" = 60'

EXHIBIT 2A



RIFFIN & ASSOCIATES, INC.

**ENCANA OIL & GAS (USA) INC.
BIG INDIAN FED 14-42-30-25**

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028


JOB No. 15045

REVISED: 4/25/07

HORZ. 1" = 50' VERT. 1" = 10'

UNGRADED ELEVATION: 6682.6'
FINISHED ELEVATION: 6681.2'

EXHIBIT 3



DRG RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

SCALE: 1" = 1 MILE

JOB No. 15045

REVISED: 4/25/07

**PROPOSED ACCESS FOR
ENCANA OIL & GAS (USA) INC.
BIG INDIAN FED 14-42-30-25**

EXISTING ROAD —————
PROPOSED ACCESS - - - - -

**TOPO MAP
A**



DRG RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

SCALE: 1" = 2000'

JOB No. 15045

REVISED: 4/25/07

**PROPOSED ACCESS ROAD FOR
ENCANA OIL & GAS (USA) INC.
BIG INDIAN FED 14-42-30-25**

ACCESS: UTILIZE ACCESS ROAD FOR BIG INDIAN 4

EXISTING ROAD
STAKED ROAD



**TOPO MAP
B**



WELL LOCATION LOOKING NORTH



WELL LOCATION LOOKING SOUTH



WELL LOCATION LOOKING WEST



WELL LOCATION LOOKING EAST




**ENCANA OIL & GAS (USA) INC.
BIG INDIAN FED 14-42-30-25**

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

JOB No. 15045

REVISED: 1/26/07

EXHIBIT 6




R. 25 E.

BIG INDIAN FED
14-42-30-25

UNGRADED ELEVATION:
6682.5'

Basis of Elevation: USGS spot
elevation located in the NW 1/4
Section 14, T30S, R25E,
Elevation: 6590'



SCALE: 1" = 1000'

T. 30 S.

LATITUDE
NORTH 38.174316 DEG.
LONGITUDE
WEST 109.150827 DEG.

NORTHING
557442.51
EASTING
2675269.37

DATUM
SPCS-UT SOUTH (NAD 27)

BHL LATITUDE
NORTH 38.173812 DEG.
BHL LONGITUDE
WEST 109.149595 DEG.

BHL
N557268
E2675628



SURVEYOR'S STATEMENT

I, Louis A. Pence, of Rock Springs, Wyoming, hereby state: This map was made from notes taken during an actual survey under my direct supervision on JANUARY 14, 2007, and it correctly shows the location of BIG INDIAN FED 14-42-30-25.

NOTES

- ◆ WELL LOCATION
- FOUND MONUMENT (BC)
- APPROXIMATE BHL




EXHIBIT 1



RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

SCALE: 1" = 1000'

JOB No. 15045

REVISED: 1/26/07

**PLAT OF DRILLING LOCATION
FOR
ENCANA OIL & GAS (USA) INC.**

**1292' F/SL & 1361' F/WL, SECTION 14,
T. 30 S., R. 25 E., SALT LAKE B.M.
SAN JUAN COUNTY, UTAH**

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 05/03/2007

API NO. ASSIGNED: 43-037-31860

WELL NAME: BIG INDIAN FED 14-42-30-25

OPERATOR: ENCANA OIL & GAS (USA) (N2175)

PHONE NUMBER: 720-876-5339

CONTACT: JEVIN CROTEAU

PROPOSED LOCATION:

SESW 14 300S 250E

SURFACE: 1292 FSL 1361 FWL

BOTTOM: 1109 FSL 1721 FWL

COUNTY: SAN JUAN

LATITUDE: 38.17422 LONGITUDE: -109.1507

UTM SURF EASTINGS: 661987 NORTHINGS: 4226555

FIELD NAME: WILDCAT (1)

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-89097

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: HNKRT

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. RLB0001191)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 05-6)
☒ RDCC Review (Y/N)
(Date: _____)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)


LOCATION AND SITING:

____ R649-2-3.
Unit: BIG INDIAN *BR*
____ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
☒ R649-3-3. Exception
____ Drilling Unit
Board Cause No: _____
Eff Date: _____
Siting: _____
☒ R649-3-11. Directional Drill

COMMENTS: _____

STIPULATIONS: _____

1. Spacing Approval
2. Spacing Study



OPERATOR: ENCANA O&G USA INC (N2175)

SEC: 10,14 T.30S R. 25E

FIELD: WILDCAT (001)

COUNTY: SAN JUAN

SPACING: R649-3-11 / DIRECTIONAL DRILLING



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

May 7, 2007

Encana Oil & Gas (USA) Inc.
370 17th St., Ste. 1700
Denver, CO 80202

Re: Big Indian Federal 14-42-30-25 Well, Surface Location 1292' FSL,
1361' FWL, SE SW, Sec. 14, T. 30 South, R. 25 East, Bottom Location
1109' FSL, 1721' FWL, SE SW, Sec. 14, T. 30 South, R. 25 East,
San Juan County, Utah


Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-037-31860.

Sincerely,


Gil Hunt
Associate Director

pab
Enclosures

cc: San Juan County Assessor
Bureau of Land Management, Moab Office

Operator: Encana Oil & Gas (USA) Inc.
Well Name & Number Big Indian Federal 14-42-30-25
API Number: 43-037-31860
Lease: UTU-89097

Surface Location: SE SW Sec. 14 T. 30 South R. 25 East
Bottom Location: SE SW Sec. 14 T. 30 South R. 25 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.
5. In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.
6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
APPLICATION FOR PERMIT TO DRILL OR REENTER



FORM APPROVED
OMB NO. 1004-0137
Expires: March 31, 2007

1a. Type of Work <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU-89097 UTU-89097	
1b. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. Indian, Allottee or Tribe Name Big Indian, #UTU-063039X	
2. Name of Operator EnCana Oil & Gas (USA) Inc.		7. If Unit or CA Agreement, Name and No. Big Indian Fed 14-42-30-25	
3a. Address 370 17th St., Suite 1700, Denver CO 80202		8. Lease Name and Well No. Big Indian Fed 14-42-30-25	
3b. Phone No. (include area code) 303-623-2300		9. API Well No. 4303731860	
4. Location of well (Report location clearly and in accordance with any State requirements. *) At surface 1292' FSL & 1361' FWL At proposed prod. zone 1109' FSL & 1721' FWL		10. Field and Pool, or Exploratory Big Indian (South)	
11. Sec., T., R., M., or Blk. And Survey or Area Sec. 14, T30S-R25E		12. County or Parish San Juan	
13. State Utah		14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE* Approximately 10 Miles SE of La Sal, UT	
15. Distance from proposed* location to nearest property or lease line, ft. 1109' BHL (Also to nearest drlg unit line, if any) 930' Unit line		16. No. of Acres in lease 2,200.00	
17. Spacing Unit dedicated to this well 40 acres		18. Distance from proposed location* to nearest well, drilling completed, applied for, on this lease, ft. Approx. 464'	
19. Proposed Depth 3217' TVD		20. BLM/ BIA Bond No. on file RLB0004733	
21. Elevations (Show whether DF, RT, GR, etc.) 6682.5' GR		22. Approximate date work will start* 15-Jul-07	
23. Estimated Duration 20 Days		24. Attachments	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1 shall be attached to this form:

- | | |
|---|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by existing bond on file (see item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/ or plans as may be required by the authorized officer. |

I hereby certify that EnCana Oil & Gas (USA) Inc. is responsible under the terms and conditions of the lease to conduct lease operations.
Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by RLB0004733.

25. Signature 	Name (Printed/ Typed) Jevin Croteau	Date 5/2/07
Title Regulatory Analyst		
Approved By (Signature) 	Name (Printed/ Typed) /s/ A. Lynn Jackson	Date 5/31/07
Title Assistant Field Manager, Division of Resources		
Office Division of Resources Moab Field Office		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

* (Instructions on page 2)


RECEIVED

AUG 03 2007

CONDITIONS OF APPROVAL ATTACHED

DIV. OF OIL, GAS & MINING

R. 25 E.




SURVEYOR'S STATEMENT

I, Louis A. Pence, of Rock Springs, Wyoming, hereby state: This map was made from notes taken during an actual survey under my direct supervision on JANUARY 14, 2007, and it correctly shows the location of BIG INDIAN FED 14-42-30-25.

NOTES

- ◆ WELL LOCATION
- FOUND MONUMENT (BC)
- APPROXIMATE BHL

EXHIBIT 1



RIFFIN & ASSOCIATES, INC.

1414 ELK ST., SUITE 202
ROCK SPRINGS, WY 82901
(307) 362-5028

SCALE: 1" = 1000'

JOB No. 15045

REVISED: 1/26/07

**PLAT OF DRILLING LOCATION
FOR
ENCANA OIL & GAS (USA) INC.**

**1292' F/SL & 1361' F/WL, SECTION 14,
T. 30 S., R. 25 E., SALT LAKE B.M.
SAN JUAN COUNTY, UTAH**

EnCana Oil & Gas (USA), Inc.
Big Indian Federal 14-42-30-25
Lease, Surface: UTU-089097
Bottom-hole: UTU-089097
Big Indian Unit (UTU-63039-X)
Location, Surface: SE/SW Section 14, T30S, R25E
Bottom-hole: SE/SW Section 14, T30S, R25E
San Juan County, Utah

A COMPLETE COPY OF THIS APPROVED PERMIT and Conditions of Approval shall be maintained on location during all construction and drilling operations, and shall be available to contractors to ensure compliance.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that EnCana Oil & Gas (USA), Inc. is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by **UT1005** (Principal – EnCana Oil & Gas (USA), Inc.) via surety consent as provided for in 43 CFR 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43 CFR 3106.7-2 continuing responsibility are met.

This permit will be valid for a period of two years from the date of approval. After permit termination, a new application must be filed for approval.

All lease operations will be conducted in full compliance with applicable regulations (43 CFR 3100), Onshore Oil and Gas Orders, lease terms, notices to lessees, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. Failure to comply with the provisions of this permit, including applicable regulations, stipulations, and/or approval conditions, will be considered a violation subject to the enforcement provisions of 43 CFR Subpart 3163.

A. DRILLING PROGRAM

1. The proposed 3M BOP system is adequate for anticipated conditions. Installation, testing and operation of the system shall be in conformance with Onshore Oil and Gas Order No. 2.
2. Concurrent approval from the State of Utah, Division of Oil, Gas & Mining (DOGM) is required before conducting any surface disturbing activities.
3. The surface casing shall extend at least 50 feet into the Chinle Formation, and shall be cemented to surface.

B. SURFACE

1. Cultural resource sites identified in the inventory reports prepared by Four Corners Archaeological Services (4-CAS Report Nos. 2615, 2616, 2622 and 2623), will be avoided during all phases of the project.
2. In order to protect watershed values, no drilling operations will be authorized between November 1 and April 30. The limitation does not apply to maintenance and operations of producing wells.
3. In order to protect wintering big game animals, no drilling operations will be authorized between November 1 and May 15. The limitation does not apply to maintenance and operation of producing wells.
4. The operator will be responsible for weed control on the disturbed areas within the limits of the well pad and road construction. The operator will be responsible for consultation with the authorized officer and/or local authorities for acceptable weed control methods.

C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

Building Location- Contact the BLM, Natural Resource Protection Specialist at least 48-hours prior to commencing construction of location.

Spud- The spud date will be reported to BLM 24-hours prior to spud. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the Moab Field Office within 24-hours after spud, regardless of whether spud was made with a dry hole digger or big rig.

Daily Drilling Reports- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the Moab Field Office on a weekly basis.

Oil and Gas Operations Reports (OGORs)- Production from this well shall be reported to Minerals Management Service (MMS) on a monthly basis.

Sundry Notices- There will be no deviation from the proposed drilling and/or workover program without prior approval. "Sundry Notices and Reports on Wells" (Form 3160-5) will be filed with the Moab Field Office for approval of all changes of plans and subsequent operations in accordance with 43 CFR 3162.3-2. Safe drilling and operating practices must be observed.

Drilling Suspensions- Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Moab Field Office. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the BLM in accordance with requirements of NTL-3A.

Cultural Resources- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Moab Field Office is to be notified.

First Production- Should the well be successfully completed for production, the Moab Field Office will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Moab Field Office. The Moab Field Office shall be notified prior to the first sale.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the Moab Field Office not later than thirty-days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. When requested, samples (cuttings and/or samples) will be submitted to the Moab Field Office.

Venting/Flaring of Gas- Gas produced from this well may not be vented/flared beyond an initial, authorized test period of 30 days or 50 MMcf, whichever first occurs, without the prior, written approval of the Moab Field Office. Should gas be vented or flared without approval beyond the authorized test period, the well may be ordered shut-in until the gas can be captured or approval to continue the venting/flaring as uneconomic is granted. In such case, compensation to the lessor (BLM) shall be required for that portion of the gas that is vented/flared without approval and which is determined to have been avoidably lost.

Produced Water- An application for approval of a permanent disposal method and location will be submitted to the Moab Field Office for approval pursuant to Onshore Oil and Gas Order No.7.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Moab Field Office for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment- If the well is completed as a dry hole, plugging instructions must be obtained from the Moab Field Office prior to initiating plugging operations.

A "Subsequent Report of Abandonment" (Form 3160-5) will be filed with the Moab Field Office within thirty-days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Moab Field Office or the appropriate surface managing agency.

TABLE 1

NOTIFICATIONS

Notify Jeff Brown (435-587-1525) BLM Monticello Field Office for the following:

2 days prior to commencement of dirt work, construction and reclamation;

1 day prior to spud;

50 feet prior to reaching the surface casing setting depth;

3 hours prior to testing BOPE.

If the person at the above number cannot be reached, notify the Moab Field Office at 435-259-2100. If unsuccessful, contact the person listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab Field Office at 435-259-2100. If approval is needed after work hours, you may contact the following:

Eric Jones, Petroleum Engineer

Office: 435-259-2117

Home: 435-259-2214

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: July 31, 2010

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU 089097

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE – Other instructions on page 2.

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator
EnCana Oil & Gas (USA) Inc.

3a. Address
370 17th Street Suite 1700 Denver, CO 80202

3b. Phone No. (include area code)
720-876-3219

7. If Unit of CA/Agreement, Name and/or No.
Big Indian #UTU-063039X

8. Well Name and No.
Big Indian Fed 14-42-30-25

9. API Well No.
43-037-31860

10. Field and Pool or Exploratory Area
Big Indian(South)

4. Location of Well (Footage, Sec., T.,R.,M., or Survey Description)
Sec 4 T30S R25E

11. Country or Parish, State
San Juan County, UT

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other Make well confidential
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.)

Please mark this well as confidential.

**CONFIDENTIAL
TIGHT HOLE**

**RECEIVED
SEP 04 2007**

DIV. OF OIL, GAS & MINING


14. I hereby certify that the foregoing is true and correct.

Name (Printed/Typed)

Susan Guidry

Title Operations Tech

Signature



Date 08/30/2007

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Encana Oil & Gas (USA) Inc
Address: 370 17th Street Suite 1700
city Denver
state Co zip 80202

Operator Account Number: N 2175

Phone Number: (720) 876-3219

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4303731860	Big Indian Fed 14-42-30-25		SESW	14	30S	25E	San Juan
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
<i>KB</i>	<i>99999</i>	<i>8124</i>	<i>9/20/2007</i>		<i>10/17/07</i>		
Comments: <i>HNKRT = HRMS</i> <i>BHL = SESW</i>							

CONFIDENTIAL

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date		Entity Assignment Effective Date		
Comments:							

ACTION CODES:

- A** - Establish new entity for new well (single well only)
- B** - Add new well to existing entity (group or unit well)
- C** - Re-assign well from one existing entity to another existing entity
- D** - Re-assign well from one existing entity to a new entity
- E** - Other (Explain in 'comments' section)

Susan Guidry

Name (Please Print)

Susan Guidry

Signature

Operations Tech

9/24/2007

Date

RECEIVED

OCT 05 2007

CONFIDENTIAL

DIV. OF OIL, GAS & MINING

REGULATORY DRILLING SUMMARY



Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/20/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 3
Spud Date :	Days From Spud : 0		Depth At 06:00 :
Morning Operations : Rig up			Estimated Total Depth :
Remarks :			
Time To	Description		
6:00 AM	Move rig & camp		

Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/19/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 2
Spud Date :	Days From Spud : -1		Depth At 06:00 :
Morning Operations : Move rig			Estimated Total Depth :
Remarks :			
Time To	Description		
12:00 PM	Wait on location		
6:00 AM	Move rig		

Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/18/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 1
Spud Date :	Days From Spud : -2		Depth At 06:00 :
Morning Operations : Wait on location			Estimated Total Depth :
Remarks :			
Time To	Description		
6:00 AM	Wait on location		

CONFIDENTIAL

REGULATORY DRILLING SUMMARY



Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/24/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 7
Spud Date : Days From Spud : 4		Depth At 06:00 : 1958
Morning Operations : Wait on wireline truck		Estimated Total Depth :
Remarks :		
Became stuck while sliding @ 1958'.		
Time To	Description	
8:00 AM	Drilling	
12:30 PM	Work tight hole, mud up, circulate to condition hole	
5:00 PM	Wiper trip 14 stds, work tight hole	
6:30 PM	Drilling	
6:00 AM	Work stuck pipe	

Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/23/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 6
Spud Date : Days From Spud : 3		Depth At 06:00 : 1852
Morning Operations : Drilling surface		Estimated Total Depth :
Remarks :		
Time To	Description	
9:30 AM	Drilling	
10:00 AM	Service rig	
2:00 PM	Drilling	
9:30 PM	Trip, pick up new directional tools, work tight hole	
6:00 AM	Directional drilling surface hole	

Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/22/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 5
Spud Date : Days From Spud : 2		Depth At 06:00 : 1184
Morning Operations : Drilling		Estimated Total Depth :
Remarks :		
Wiper trip went well.		
Time To	Description	
9:30 AM	Drilling	
10:00 AM	Service rig	
12:00 AM	Drilling	
3:00 AM	Wiper trip 15 stds	
6:00 AM	directional drilling 12.25 " surface hole	

Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/21/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 4
Spud Date : Days From Spud : 1		Depth At 06:00 : 485
Morning Operations : Directional drilling surface hole		Estimated Total Depth :
Remarks :		
Spud @ 14:30 hrs 9/20/07.		
Time To	Description	
2:30 PM	Rig up	
7:00 PM	Drilling surface hole	
8:00 PM	Scribe tools / adj motor	
6:00 AM	Directional drilling surface hole	

REGULATORY DRILLING SUMMARY



Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/27/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 10
Spud Date :	Days From Spud : 7	Depth At 06:00 : 19580
Morning Operations : W.O Orders		Estimated Total Depth :

Remarks :

Time To	Description
1:30 PM	L.D.D.P. & H.W.D.P
4:00 PM	Pick up Directional tools bend motor 1.83
5:30 PM	Pick up DC & Jars
9:00 PM	W.O. orders
11:00 PM	Pick up H.W.D.P try to tag cement
3:15 AM	Work on tight hole
6:00 AM	Trip out & W.O.Orders

Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/26/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 9
Spud Date :	Days From Spud : 6	Depth At 06:00 : 1958
Morning Operations : W.O.cement		Estimated Total Depth :

Remarks :

Bottom Plug From 1400 To 100 Top Plug From 650 To 500 Will Sit Surface @ 2200 Resevd order from Eric Jonse Of BLM On 9/25/07

Time To	Description
10:30 AM	Run Free Point
12:00 PM	Trip
3:00 PM	W.O.O
7:00 PM	W.O.Cementers
9:00 PM	Trip In hole
1:30 AM	Circ. W.O Cementers
2:00 AM	Mix Pump 400sxPlug
2:30 AM	Pull 9 STDS
3:00 AM	Circ.
4:00 AM	Mix & Pump 150 sx
4:30 AM	Circ.
5:00 AM	Trip Out
6:00 AM	W.O.Cement

Well : Big Indian Federal 14-42-30-25	API # : 4303731860	Operations Date : 09/25/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM	Area : Big Indian	Report # : 8
Spud Date :	Days From Spud : 5	Depth At 06:00 : 1958
Morning Operations : Wireline freepoint run		Estimated Total Depth :

Remarks :

Stuck below top drill collar

Time To	Description
7:00 AM	Work tight hole
12:30 PM	Run wireline freepoint
8:00 PM	Displace hole w/ wtr, Jarring on stuck pipe
10:30 PM	Run wireline freepoint
5:00 AM	Jarring on string
6:00 AM	Run wireline freepoint

CONFIDENTIAL

REGULATORY DRILLING SUMMARY



Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/30/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 13
Spud Date :	Days From Spud : 10		Depth At 06:00 : 911
Morning Operations : Drilling			Estimated Total Depth :
Remarks :			
Time To	Description		
8:00 AM	Lay Down DC & Jars		
10:00 AM	Trip in W/ Directional tools & 3 STDS DC		
11:00 AM	Pick up Kelly & Ream Down		
6:00 AM	Drilling 360 to 911		

Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/29/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 12
Spud Date :	Days From Spud : 9		Depth At 06:00 :
Morning Operations : Drill Top of cmt			Estimated Total Depth :
Remarks :			
Top cmt plug @ 310 Drill to 346 cmt OK tripping out to pick up Directional tools			
Time To	Description		
5:00 AM	W.O.Cement		
6:00 AM	Trip in tag cmt & Drill top cmt plug		

Well : Big Indian Federal 14-42-30-25		API # : 4303731860	Operations Date : 09/28/2007
Surface Location : SESW Sec 14 T30S - R25E 6th PM		Area : Big Indian	Report # : 11
Spud Date :	Days From Spud : 8		Depth At 06:00 :
Morning Operations : Trip In 21 jts to set plug			Estimated Total Depth :
Remarks :			
Time To	Description		
11:00 AM	W.O.Orders		
1:00 PM	Trip in lay down 8 61/4 DC & Jars		
1:00 AM	W.O.Halliburton		
3:00 AM	Trip in 21 jts into set plug		
4:30 AM	W.O.Halliburton		
5:15 AM	Rig up & Mix Pump CMT Plug @ 650 to 350		
6:00 AM	W.O.Cement		

CMT Permium - Glass-G 300 sks 17# YLD.1.0 53.4 bbls.
Salt 3% CFR-3 W/O Defoamer 50 bbl sk D-Air 3000l 5
gal.pail
Plug @ 650 to 350 W.O.Cement 24hrs 0500 28 / 07 to
0500 29 / 07

CONFIDENTIAL

REGULATORY DRILLING SUMMARY



Well : **Big Indian Federal 14-42-30-25**
Surface Location : **SESW Sec 14 T30S - R25E 6th PM**
Spud Date : Days From Spud : 13
Morning Operations : W.O.Cement

API # : 4303731860
Area : Big Indian

Operations Date : 10/03/2007
Report # : 16
Depth At 06:00 :
Estimated Total Depth :

Remarks :

Time To	Description
7:00 AM	Circ. & Pump Sweep 50 bbls
10:00 AM	Short Trip
11:30 AM	Circ. & Pump 120 bbl Sweep
2:30 PM	Trip out to run 9 5/8 csg
3:30 PM	Lay Down Directional Tools
7:00 PM	Rig up Run 9 5/8 csg
8:00 PM	Rig up Circ.
9:30 PM	mix & Pump CMT
2:30 AM	W.O.CMT
4:30 AM	Cut Off Conductor & 9 5/8 csg
6:00 AM	W.O.Wellhead

Well : **Big Indian Federal 14-42-30-25**
Surface Location : **SESW Sec 14 T30S - R25E 6th PM**
Spud Date : Days From Spud : 12
Morning Operations : Circ. TD 2295

API # : 4303731860
Area : Big Indian

Operations Date : 10/02/2007
Report # : 15
Depth At 06:00 : 2295
Estimated Total Depth :

Remarks :

TD @0500 2295 10/2/07 Circ. 1.1/2 hrs short trip circ. 1.1/2 hrs & run 9 5/8 csg

Time To	Description
5:00 AM	Drilling
6:00 AM	Circ.

Well : **Big Indian Federal 14-42-30-25**
Surface Location : **SESW Sec 14 T30S - R25E 6th PM**
Spud Date : Days From Spud : 11
Morning Operations : Drilling

API # : 4303731860
Area : Big Indian

Operations Date : 10/01/2007
Report # : 14
Depth At 06:00 : 1760
Estimated Total Depth :

Remarks :

Time To	Description
11:30 AM	Drilling
12:30 PM	Repair gear box on rig
12:00 AM	Drilling
2:30 AM	Weid sieve on kelly bushing
6:00 AM	Drilling

RECEIVED

OCT 09 2007

DIV. OF OIL, GAS & MINING

CONFIDENTIAL



CONFIDENTIAL

pason systems usa corp.

16100 Table Mountain Parkway • Ste. 100 • Golden • CO • 80403
Telephone (720) 880-2000 • Fax (720) 880-0016
www.pason.com

43-037-31860
14 30s 25e

October 10, 2007

Utah Division of Oil, Gas & Mining
P.O. Box 145801
Salt Lake City, UT 84114-5801

**RE: ENCANA OIL & GAS (USA), INC.
BIG INDIAN FEDERAL 14-42-30-25
SEC. 14, T30S, R25E
SAN JUAN COUNTY, UT**

To Whom It May Concern:

Enclosed is the final computer colored log for the above referenced well.

We appreciate the opportunity to be of service to you and look forward to working with you in the near future.

If you have any questions regarding the enclosed data, please contact us.

Sincerely,

Bill Nagel

Bill Nagel
Geology Manager
Pason Systems USA
BN/gdr

Encl: 1 Computer Colored Log.

Cc: Stephen Schurger, EnCana Oil & Gas (USA), Inc., Denver, CO.

RECEIVED

OCT 12 2007

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

CONFIDENTIAL

FORM APPROVED
OMB NO. 1004-0137
Expires: July 31, 2010

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☐ Oil Well ☒ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☐ New Well ☒ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resvr.,
Other: _____

2. Name of Operator
EnCana Oil & Gas (USA) Inc.

3. Address 370 17th Street Suite 1700 Denver CO 80202

3a. Phone No. (include area code)
720-876-3219

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

1292' FSL & 1361' FWL
At surface

At top prod. interval reported below

At total depth 1364 FSL 1771 FWL per DKD

14. Date Spudded
09/20/2007

15. Date T.D. Reached
10/05/2007

16. Date Completed 11/09/2007
☐ D & A ☒ Ready to Prod.

5. Lease Serial No.
UTU 089097

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
Big Indian # UTU 063039X

8. Lease Name and Well No.
Big Indian Fed 14-42-30-25

9. AFI Well No.
4303731860

10. Field and Pool or Exploratory
Big Indian(South)

11. Sec., T., R., M., on Block and
Survey or Area Sec 14 T30S R25E

12. County or Parish

13. State

San Juan

UT

17. Elevations (DF, RKB, RT, GL)*

18. Total Depth: MD 3365'
TVD 3322.76'

19. Plug Back T.D.: MD
TVD

20. Depth Bridge Plug Set: MD
TVD

21. Type Electric & Other Mechanical Logs Run (Submit copy of each)

CBL SD, DSN, ACTR

22. Was well cored? ☐ No ☐ Yes (Submit analysis)
Was DST run? ☐ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☐ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12.25	9.625"	36#	Surface	2277'	2277'	790		surface	
8.75	5.5"	17#	1850'	3352'	3352'	340		1850'	

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2 3/8"	3050'							

25. Producing Intervals

Formation	Top	Bottom	Perforation Interval	Size	No. Holes	Perf. Status
A) Cutler			2582'-2630'	3 3/8"	78	
B) HART			2816'-2860'	3 3/8"	76	
C)			2900'-2940'	3 3/8"	62	
D)			2980'-3108'	3 3/8"	284	

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
3083'-3108'	486.75 barrels of water 30198# 20/40 jordan-unimin sand N2 313 Mscf F052 64.5 gal B145 11.8 gal
2980'-3030'	576.54 barrels of water 39840# 20/40 jordan-unimin sand;N2 400 mscf;F052 83.9 gal;B145 12.9 gal
2900'-2940'	562.50 barrels water;39000# 20/40 jordan-unimin sand;N2 410,240 scf;F052 79.6 gal; B145 15.1 gal
2816'-2860'	550 barrels water;38526# 20/40 jordan-unimin sand; N2 330 mscf; F052 68.8 gal; B145 15.1 gal

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
10/27/07	10/27/07	24	→	2	919	38			
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
28/64	280	400	→	2	919	38		Producing	

RECEIVED
DEC 10 2007

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

DIV. OF OIL, GAS & MINING

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	

29. Disposition of Gas (*Solid, used for fuel, vented, etc.*)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				Cutler	3031'
				Honaker Trail	3083'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☐ Directional Survey
☐ Sundry Notice for plugging and cement verification
☐ Core Analysis
☐ Other:

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Susan Guidry

Title Operations Tech

Signature

Date

12/5/07

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)



DEC 10 2007

DIV OF OIL, GAS & MINING

Downhole Schematic for Big Indian Fed 14-42-30-25



Project :Paradox

API # :4303731860

Surface Location : SESW Sec 14 T30S - R25E 6th PI

Area : Big Indian

County : SAN JUAN


BHL : SESW-14-30S-25 E 6th PM

As Of : 10/23/2007

GL : 6682.5 ft

KB to GL : 10.0 ft

KB : 6692.5 ft



Casing Details								
Section	Hole	Casing	Mass	Set At	Length	Thread	Grade	Description
Surface	12.250	10"	0	2,277	1	ST&C		Guide shoe
		9.625"	36	2,276	42	ST&C	J-55	Casing
		10"	0	2,234	1	ST&C		Float collar
		9.625"	36	2,233	2,236	ST&C	J-55	Casing
Production	8.750	5.5	17	3,352	1	LT&C	P-110	Float shoe
		5.5	17	3,351	28	LT&C	I-80	Casing
		5.5	17	3,323	1	LT&C	P-110	Float Collar
		5.5	17	3,322	1,068	LT&C	I-80	Casing
		5.5	17	2,253	33	LT&C	I-80	Casing
		5.5	17	2,220	2,223	LT&C	I-80	Casing

Cement Details				Blend / Additives	
Section	Sequence	Top	Density		
Surface	Lead	0	12.5	Class G / 2.0% D079, 0.25#/sk D029, 0.2% D046	
	Tail	0	15.8	Class G / 0.25#/sk D029	
Production	Lead	1,850	13.0	50:50 poz / 5%D20, 4lb/sk D24, .275%D167, .1%D65, .15%D800, .1%D46, 0.25lb/sk D29	

Tubing and Downhole Equipment			
O.D.	Length	Depth	Description
0.000	10.00	10.00	KB
2.375	3,000.15	3,010.15	93 jts 2-3/8 tbg
0.000	1.00	3,011.15	1- 1.87 F/N
2.375	31.20	3,042.35	1- jt 2-3/8 tbg
0.000	1.00	3,043.35	1- 1.81 F/N
2.375	6.00	3,049.35	1- 6' x 2-3/8 pup jt
0.000	0.65	3,050.00	1- REG

Perforations					Stage 4			
Stage 1	Date	From	To	Shots	Stage 4	Date	From	To
	10/15/2007	3,083	3,108	100		10/16/2007	2,846	2,860
Stage 2							2,816	2,840
	10/15/2007	3,000	3,030	120	Stage 5	Date	From	To
		2,980	2,996	64		10/16/2007	2,624	2,630
Stage 3							2,611	2,622
	10/16/2007	2,921	2,940	38			2,601	2,608
		2,900	2,912	24			2,582	2,597
								30

Frac Summary
 Stage 1 : No Frac
 Stage 2 : No Frac
 Stage 3 : No Frac
 Stage 4 : No Frac
 Stage 5 : No Frac

Bridge Plug Details			
Depth	Date Set	Plug Type	Sacks Cement
3,040.0	10/15/2007	CBP	0
2,870.0	10/16/2007	CBP	0
2,550.0	10/17/2007	CBP	0
2,950.0	10/15/2007	CBP	0

CBP at 3,040.0 drilled out 10/20/2007
 CBP at 2,870.0 drilled out 10/18/2007
 CBP at 2,550.0 drilled out 10/18/2007
 CBP at 2,950.0 drilled out 10/19/2007

RECEIVED

DEC 10 2007

DIV. OF OIL, GAS & MINING

Downhole Schematic for Big Indian Fed 14-42-30-25



Project :Paradox

Area : Big Indian

As Of : 10/23/2007

API # :4303731860

County : SAN JUAN


GL : 6682.5 ft

Surface Location : SESW Sec 14 T30S - R25E 6th PI

BHL : SESW-14-30S-25 E 6th PM

KB to GL : 10.0 ft



KB : 6692.5 ft



Casing Details									
Section	Hole	Casing	Mass	Set At	Length	Thread	Grade	Description	
Surface	12.250	10"	0	2,277	1	ST&C		Guide shoe	
		9.625"	36	2,276	42	ST&C	J-55	Casing	
		10"	0	2,234	1	ST&C		Float collar	
		9.625"	36	2,233	2,236	ST&C	J-55	Casing	
Production	8.750	5.5	17	3,352	1	LT&C	P-110	Float shoe	
		5.5	17	3,351	28	LT&C	I-80	Casing	
		5.5	17	3,323	1	LT&C	P-110	Float Collar	
		5.5	17	3,322	1,068	LT&C	I-80	Casing	
		5.5	17	2,253	33	LT&C	I-80	Casing	
		5.5	17	2,220	2,223	LT&C	I-80	Casing	
Cement Details									
Section	Sequence	Top	Density	Blend / Additives					
Surface	Lead	0	12.5	Class G / 2.0% D079, 0.25#/sk D029, 0.2% D046					
	Tail	0	15.8	Class G / 0.25#/sk D029					
Production	Lead	1,850	13.0	50:50 poz / 5%D20,4lb/skD24,.275%D167,.1%D65,.15%D800,.1%D46, 0.25lb/sk D29					
Tubing and Downhole Equipment									
O.D.	Length	Depth	Description						
0.000	10.00	10.00	KB						
2.375	3,000.15	3,010.15	93 jts 2-3/8 tbg						
0.000	1.00	3,011.15	1- 1.87 F/N						
2.375	31.20	3,042.35	1- jt 2-3/8 tbg						
0.000	1.00	3,043.35	1- 1.81 F/N						
2.375	6.00	3,049.35	1- 6' x 2-3/8 pup jt						
0.000	0.65	3,050.00	1- REG						
Perforations									
Stage 1					Stage 4				
	Date	From	To	Shots		Date	From	To	Shots
	10/15/2007	3,083	3,108	100		10/16/2007	2,846	2,860	28
Stage 2							2,816	2,840	48
	Date	From	To	Shots	Stage 5				
	10/15/2007	3,000	3,030	120		Date	From	To	Shots
		2,980	2,996	64		10/16/2007	2,624	2,630	12
Stage 3							2,611	2,622	22
	Date	From	To	Shots			2,601	2,608	14
	10/16/2007	2,921	2,940	38			2,582	2,597	30
		2,900	2,912	24					
Frac Summary									
Stage 1 : No Frac									
Stage 2 : No Frac									
Stage 3 : No Frac									
Stage 4 : No Frac									
Stage 5 : No Frac									
Bridge Plug Details									
Depth	Date Set	Plug Type	Sacks Cement						
3,040.0	10/15/2007	CBP	0						
2,870.0	10/16/2007	CBP	0						
2,550.0	10/17/2007	CBP	0						
2,950.0	10/15/2007	CBP	0						
CBP at 3,040.0 drilled out 10/20/2007									
CBP at 2,870.0 drilled out 10/18/2007									
CBP at 2,550.0 drilled out 10/18/2007									
CBP at 2,950.0 drilled out 10/19/2007									



Project: Paradox (Nad 27)
 Site: Sec14-T30S-R25E
 Well: Big Indian Fed 14-42-30-25
 Wellbore: STK #1
 Design: Final Survey



Azimuths to True North
 Magnetic North: 11.11°

Magnetic Field
 Strength: 51742.0nT
 Dip Angle: 64.51°
 Date: 9/25/2007
 Model: IGRF200510

DESIGN DETAILS: STK #1

75392; JS
 WELL @ 6680.0ft (Original Well Elev)

Azimuth	Origin	N/S	E/W	From TVD
Big Indian Fed 14-42-30-25 BHL2	Slot	0.0	0.0	0.0

Cathedral Energy Services

Survey Report

Company: EnCana Oil & Gas (USA) Inc
Project: Paradox (Nad 27)
Site: Sec14-T30S-R25E
Well: Big Indian Fed 14-42-30-25
Wellbore: STK #1
Design: STK #1

Local Co-ordinate Reference: Well Big Indian Fed 14-42-30-25
TVD Reference: WELL @ 6680.0ft (Original Well Elev)
MD Reference: WELL @ 6680.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 US Multi User Db

Project	Paradox (Nad 27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah South 4303		

Site	Sec14-T30S-R25E			
Site Position:		Northing:	558,896.82 ft	Latitude: 38.178374
From:	Lat/Long	Easting:	2,674,316.18 ft	Longitude: -109.154015
Position Uncertainty:	0.0 ft	Spot Radius:	"	Grid Convergence: 1.44 °

Well	Big Indian Fed 14-42-30-25			
Well Position	+N/-S	0.0 ft	Northing:	557,442.55 ft
	+E/-W	0.0 ft	Easting:	2,675,269.45 ft
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft
			Ground Level:	6,660.0 ft

Wellbore	STK #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	9/25/2007	11.11	64.51	51,742

Design	STK #1			
Audit Notes:				
Version:	1.0	Phase:	ACTUAL	Tie On Depth: 304.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction
	(ft)	(ft)	(ft)	(°)
	0.0	0.0	0.0	77.24

Survey Program	Date	11/5/2007		
From	To	Survey (Wellbore)	Tool Name	Description
(ft)	(ft)			
109.0	304.0	Survey #1 (DD)	MWD	Geolink MWD
383.0	3,310.0	Survey #1 (STK #1)	MWD	Geolink MWD

Survey									
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Vertical	Dogleg	Build	Formations /
Depth	(°)	(°)	Depth	(ft)	(ft)	Section	Rate	Rate	Comments
(ft)			(ft)			(ft)	(°/100ft)	(°/100ft)	
304.0	9.90	84.10	303.3	1.4	13.6	13.6	0.00	0.00	
383.0	9.80	85.90	381.1	2.5	27.1	27.0	0.41	-0.13	
475.0	10.00	83.60	471.7	4.0	42.8	42.7	0.48	0.22	
560.0	11.20	79.50	555.3	6.3	58.3	58.2	1.67	1.41	
652.0	11.60	79.00	645.5	9.7	76.1	76.4	0.45	0.43	
743.0	11.80	78.10	734.6	13.4	94.2	94.9	0.30	0.22	
841.0	11.90	74.10	830.5	18.2	113.8	115.0	0.84	0.10	
933.0	11.70	73.60	920.5	23.4	131.8	133.8	0.24	-0.22	
1,025.0	11.70	73.20	1,010.6	28.8	149.7	152.4	0.09	0.00	
1,117.0	11.90	73.20	1,100.7	34.2	167.7	171.1	0.22	0.22	
1,209.0	11.80	73.80	1,190.7	39.6	185.8	190.0	0.17	-0.11	
1,303.0	11.40	73.30	1,282.8	44.9	204.0	208.8	0.44	-0.43	

Cathedral Energy Services

Survey Report

Company: EnCana Oil & Gas (USA) Inc
Project: Paradox (Nad 27)
Site: Sec14-T30S-R25E
Well: Big Indian Fed 14-42-30-25
Wellbore: STK #1
Design: STK #1

Local Co-ordinate Reference: Well Big Indian Fed 14-42-30-25
TVD Reference: WELL @ 6680.0ft (Original Well Elev)
MD Reference: WELL @ 6680.0ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 2003.16 US Multi User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Formations / Comments
1,396.0	12.10	73.90	1,373.9	50.3	222.1	227.7	0.76	0.75	
1,492.0	12.20	72.70	1,467.7	56.1	241.5	247.9	0.28	0.10	
1,588.0	12.10	74.70	1,561.6	61.8	260.9	268.1	0.45	-0.10	
1,683.0	12.10	75.90	1,654.4	66.8	280.1	288.0	0.26	0.00	
1,778.0	12.20	75.20	1,747.3	71.8	299.5	308.0	0.19	0.11	
1,873.0	12.50	73.60	1,840.1	77.3	319.1	328.2	0.48	0.32	
1,968.0	11.80	75.60	1,933.0	82.6	338.3	348.2	0.86	-0.74	
2,064.0	9.80	82.30	2,027.3	86.1	355.9	366.2	2.46	-2.08	
2,159.0	9.10	86.00	2,121.0	87.7	371.4	381.6	0.98	-0.74	
2,226.0	9.40	87.50	2,187.1	88.3	382.2	392.3	0.57	0.45	
2,312.0	9.40	87.00	2,272.0	89.0	396.2	406.1	0.09	0.00	
2,408.0	6.10	84.20	2,367.1	89.9	409.1	418.9	3.46	-3.44	
2,503.0	2.40	103.70	2,461.8	90.0	416.1	425.7	4.13	-3.89	
2,599.0	2.10	119.20	2,557.7	88.6	419.6	428.8	0.70	-0.31	
2,694.0	2.20	160.70	2,652.7	86.1	421.7	430.3	1.61	0.11	
2,789.0	3.50	188.20	2,747.6	81.5	421.9	429.5	1.95	1.37	
2,884.0	1.30	212.60	2,842.5	77.7	420.9	427.7	2.50	-2.32	
2,979.0	0.70	327.90	2,937.5	77.3	420.0	426.7	1.81	-0.63	
3,074.0	0.90	287.50	3,032.5	78.0	419.0	425.9	0.61	0.21	
3,170.0	2.10	241.00	3,128.4	77.4	416.7	423.5	1.69	1.25	
3,310.0	4.40	231.00	3,268.2	72.7	410.3	416.2	1.69	1.64	Last DP Stk Survey @ 3310' MD

Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
Big Indian Fed 14-42-30- - survey misses by 19.6ft at 3258.7ft MD (3217.0 TVD, 74.9 N, 413.1 E) - Circle (radius 50.0)	0.00	0.00	3,217.0	91.0	402.0	557,543.66	2,675,668.99	38.174566	-109.149429
Big Indian Fed 14-42-30- - survey misses by 6.1ft at 2397.0ft MD (2356.2 TVD, 89.8 N, 407.9 E) - Point	0.00	0.00	2,357.0	90.9	402.0	557,543.52	2,675,668.99	38.174566	-109.149429

Survey Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
3,310.0	3,268.2	72.7	410.3	Last DP Stk Survey @ 3310' MD

Checked By: _____ Approved By: _____ Date: _____

Amended WELLBORE DIAGRAM

Surface Loc:

Log Tops

Cutler 3031'
Honaker Trail 3083'

KB 6692.5
GL 6692.5

Original Borehole

Sidetrack

Top Plug 350'-650'

Bottom Plug 1000'-1400'

Top of Cutler Formation 3031'

EOT @ 3050'

Top of Honaker Trail Formation 3083'

3365'

Operator: EnCana Oil & Gas (USA) Inc.
Well Name: Big Indian Fed 14-42-30-25
Lease Number: UTU 089097
Location: SESW Sec 14 T30S R25E
Field: Big Indian South
County: San Juan
API Number: 43-037-31860-00
Diagram Date: 04/16/2008

Well History

Spud Date 09/20/2007
TD Reached 10/05/2007
Rig Released 10/07/2007
Completion Date 11/09/2007
First Sales: 10/27/2007

55 jts 9.625" 36# J-55 ST&C
csg @ 2277'; cmt w/ 590 sx
Type III lead; 200 sx Type III tail

2582'-2630'
Cutler Perfs shot 10/16/07 (78 holes)
3-3/8", 4 SPF, 90° phasing

2816'-2860'
Cutler Perfs shot 10/16/07 (76 holes)
3-3/8", 4 SPF, 90° phasing

2900'-2940'
Cutler Perfs shot 10/15/07 (184 holes)
3-3/8", 4 SPF, 90° phasing

2980'-3108'
Honaker Trail Perfs shot 10/15/07 (100 holes)
3-3/8", 4 SPF, 90° phasing

79 jts 5.5" 17# I-80&P-110 LT&C csg @ 3352'
Cmt w/ 340 sx G 50/50 Poz

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING

CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

5/14/2010

FROM: (Old Operator): N2175-EnCana Oil & Gas (USA) Inc. 370 17th Street, Suite 1700 Denver, CO 80202 Phone: 1 (303) 623-2300				TO: (New Operator): N3670-Patara Oil & Gas, LLC 333 Clay Street, Suite 3960 Houston, TX 77002 Phone: 1 (713) 357-7171			
CA No.				Unit: BIG INDIAN			
WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE
SEE ATTACHED							
WELL STATUS							

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/11/2010
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/11/2010
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 5/11/2010
- a. Is the new operator registered in the State of Utah: Business Number: 7655540-0161
- a. (R649-9-2) Waste Management Plan has been received on: * * requested 9/27/10
- b. Inspections of LA PA state/fee well sites complete on: * * requested 9/27/10
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 6/29/2010
Lisbon B-816 only

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/14/2010
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/14/2010
- Bond information entered in RBDMS on: 9/14/2010
- Fee/State wells attached to bond in RBDMS on: 9/14/2010
- Injection Projects to new operator in RBDMS on: 9/14/2010
- Receipt of Acceptance of Drilling Procedures for APD/New on: 5/11/2010

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000428
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number RLB0013207 & B006008
- b. The **FORMER** operator has requested a release of liability from their bond on: not yet

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: ENCANA OIL & GAS (USA) INC. <i>N2175</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 370 17th Street, Suite 1700 CITY Denver STATE CO ZIP 80202 PHONE NUMBER: (303) 623-2300		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached List COUNTY:		8. WELL NAME and NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input checked="" type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective May 4, 2010 Patara Oil & Gas LLC, 333 Clay Street, Suite 3960, Houston, TX 77002, will take over completions and operations and is designated as agent operator for the subject wells on the attached list.

Bond coverage for all activities will be covered by Patara's BLM Statewide Oil & Gas Bond No. UTB000428 and UDOGM Bond No. Pending. *RIB 0013207 + B 006008*

Patara Oil & Gas LLC, Lane M. Kincannon, Vice-President, Land & Business Development *N3670*

Signature *[Signature]* Date 5/4/2010

NAME (PLEASE PRINT) <u>Ricardo D. Gallegos</u>	TITLE <u>Attorney-in-Fact</u>
SIGNATURE <i>[Signature]</i>	DATE <u>5/4/2010</u>

(This space for State use only)

APPROVED 9/14/2010
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED
May 11 2010 ER
DIV. OF OIL, GAS & MINING

ENCANA O-G (N2175) to PATARA O-G (N3670)
effective May 4, 2010
BIG INDIAN

well_name	sec	twp	rng	api	entity	lease	well	stat	C
BIG INDIAN UNIT 1	33	290S	240E	4303716219	8122	Federal	OW	S	
BIG INDIAN 4	14	300S	250E	4303716221	8124	Federal	GW	S	
					8124				
BIG INDIAN FED 14-21-30-25	14	300S	250E	4303731850	16377	Federal	GW	P	
BIG INDIAN FED 15-24-30-25	14	300S	250E	4303731859	8124	Federal	GW	S	
BIG INDIAN FED 14-42-30-25	14	300S	250E	4303731860	8124	Federal	GW	P	
BIG INDIAN FED 15-24B-30-25	14	300S	250E	4303731883	8124	Federal	GW	S	
BIG INDIAN FED 23-13B-30-25	23	300S	250E	4303731884		Federal	GW	APD	C
BIG INDIAN FED 23-13-30-25	23	300S	250E	4303731885		Federal	GW	APD	C

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-89097
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: 7. UNIT or CA AGREEMENT NAME: BIG INDIAN
2. NAME OF OPERATOR: PATARA OIL & GAS, LLC		8. WELL NAME and NUMBER: BIG INDIAN FED 14-42-30-25
3. ADDRESS OF OPERATOR: 600 17th Street Ste 1900S , Denver, CO, 80202		9. API NUMBER: 43037318600000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1292 FSL 1361 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 14 Township: 30.0S Range: 25.0E Meridian: S		9. FIELD and POOL or WILDCAT: BIG INDIAN (HERMOSA)
		COUNTY: SAN JUAN
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input checked="" type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/6/2012	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Patara has completed operations to pull the submersible pump & rods in order to clean off scale and salt build up on the downhole equipment. Production had fallen off due to fill in the hole, from ± 176 mcf/d to 0 mcf/d. Post production enhancement, the well has returned to ± 200 mcf/d. Thank you.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY November 28, 2012		
NAME (PLEASE PRINT) Christopher Noonan	PHONE NUMBER 303 563-5377	TITLE Supervisor: Regulations & Production
SIGNATURE N/A	DATE 11/21/2012	

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET (for state use only)

ROUTING

CDW

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

11/1/2012

FROM: (Old Operator): N3670- Patara Oil & Gas, LLC 600 17th Street, Suite 1900S Denver, CO 80202 Phone: 1 (303) 825-0685	TO: (New Operator): N3645- CCI Paradox Upstream, LLC 600 17th Street, Suite 1900S Denver, CO 80202 Phone: 1 (303) 825-0685
---	--

CA No.				Unit:	Big Indian			
WELL NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
See Attached List								

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 1/23/2013
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 2/7/2013
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/12/2013
- a. Is the new operator registered in the State of Utah: Business Number: 8523441-0161
- a. (R649-9-2) Waste Management Plan has been received on: Not Yet
- b. Inspections of LA PA state/fee well sites complete on: N/A
- c. Reports current for Production/Disposition & Sundries on: 2/12/2013
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM Not Yet BIA N/A
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: Not Yet
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 2/12/2013
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 2/12/2013
- Bond information entered in RBDMS on: 2/7/2013
- Fee/State wells attached to bond in RBDMS on: 2/12/2013
- Injection Projects to new operator in RBDMS on: N/A
- Receipt of Acceptance of Drilling Procedures for APD/New on: 2/4/2013

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: 105865919
- Indian well(s) covered by Bond Number: N/A
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 105865922
- b. The **FORMER** operator has requested a release of liability from their bond on: N/A

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

Patara Oil Gas, LLC (N3670) to CCI Paradox Upstream, LLC (N3945)

Effective 11/1/2012

Big Indian Unit

Well Name	Section	TWN	RNG	API Number	Entity	Lease Type	Well Type	Well Status
BIG INDIAN FED 23-13B-30-25	23	300S	250E	4303731884		Federal	GW	APD
BIG INDIAN FED 23-13-30-25	23	300S	250E	4303731885		Federal	GW	APD
BIG INDIAN FED 14-42-30-25	14	300S	250E	4303731860	8124	Federal	GW	P
BIG INDIAN UNIT 1	33	290S	240E	4303716219	8122	Federal	OW	S
BIG INDIAN 4	14	300S	250E	4303716221	8124	Federal	GW	S
BIG INDIAN FED 14-21-30-25	14	300S	250E	4303731850	8124/16377	Federal	GW	S
BIG INDIAN FED 15-24-30-25	14	300S	250E	4303731859	8124	Federal	GW	S
BIG INDIAN FED 15-24B-30-25	14	300S	250E	4303731883	8124	Federal	GW	S

RECEIVED

JAN 23 2013

FORM 9

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

DIV. OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Multiple Well Transfer</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: n/a
2. NAME OF OPERATOR: Patara Oil & Gas LLC <u>N3670</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 600 17th St. Ste. 1900S City Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME: n/a
PHONE NUMBER: (303) 825-0685		8. WELL NAME and NUMBER: Multiple
4. LOCATION OF WELL FOOTAGES AT SURFACE: n/a		9. API NUMBER: n/a
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT: n/a

COUNTY: San Juan, UT

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 11/1/2012	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Patara Oil & Gas LLC (Patara) hereby requests the transfer of operating rights and responsibilities for the subject wells, listed herein, to the new owner/operator of the assets, being effective November 1, 2012; CCI Paradox Upstream LLC (CCI).

Please see Exhibit I for a detailed list of upstream assets considered for transfer. Patara midstream assets will be transferred via a separate letter, enclosed.

NAME (PLEASE PRINT) Christopher A. Noonan TITLE Regulations & Production Reporting Supervisor
SIGNATURE *Christopher A. Noonan* DATE 1/18/13

(This space for State use only)

APPROVED

FEB 12 2013

(5/2000)

DIV. OF OIL, GAS & MINING

(See Instructions on Reverse Side)

BY: Rachel Medina

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Multiple Well Transfer</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: n/a
2. NAME OF OPERATOR: CCI Paradox Upstream LLC <u>N3945</u>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: n/a
3. ADDRESS OF OPERATOR: 600 17th St. Ste. 1900S CITY <u>Denver</u> STATE <u>CO</u> ZIP <u>80202</u>		7. UNIT or CA AGREEMENT NAME: n/a
4. LOCATION OF WELL FOOTAGES AT SURFACE: <u>n/a</u>		8. WELL NAME and NUMBER: <u>Multiple</u>
PHONE NUMBER: <u>(303) 825-0685</u>		9. API NUMBER: n/a
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT: n/a

COUNTY: San Juan, UT

STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: <u>11/1/2012</u>	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

CCI Paradox Upstream LLC (CCI), hereby requests the transfer of operating rights and responsibilities for the subject wells, listed herein, to the new owner/operator of the assets, CCI, being effective November 1, 2012. The assets were previously operated by Patara Oil & Gas LLC (Patara) prior to sale.

Please see Exhibit I for a detailed list of upstream assets considered for transfer. Patara midstream assets will be transferred via a separate letter, enclosed.

Bond Number:
BLM: 105865919
State: 105865922

NAME (PLEASE PRINT) <u>Christopher A. Noonan</u>	TITLE <u>Regulations & Production Reporting Supervisor</u>
SIGNATURE 	DATE <u>2/6/2012</u>

(This space for State use only)

APPROVED

FEB 12 2013

DIV. OIL GAS & MINING

BY: Rachel Medina

RECEIVED

FEB 07 2013

Div. of Oil, Gas & Mining

Exhibit I

BLM Form 3160-5 Transfer of Operator

Utah Form 9 Transfer of Operator

State of Utah Upstream Assets

01/09/2013

API Well Number	Operator	Well Name	Well Status	Well Type	Field Name	County	Qtr/Qtr	Section	Township-Range)
✓ 43-037-15049-00-00	PATARA OIL & GAS LLC	LISBON D-616	Shut-In	Oil Well	LISBON	SAN JUAN	NENE	16	30S-24E 1
✓ 43-037-15123-00-00	PATARA OIL & GAS LLC	LISBON B-615	Producing	Oil Well	LISBON	SAN JUAN	NENW	15	30S-24E 2
✓ 43-037-15769-00-00	PATARA OIL & GAS LLC	LISBON B912	Shut-In	Oil Well	LISBON	SAN JUAN	SESW	12	30S-24E 3
✓ 43-037-16219-00-00	PATARA OIL & GAS LLC	BIG INDIAN UNIT 1	Shut-In	Oil Well	BIG INDIAN (MADISON)	SAN JUAN	SENE	33	29S-24E 11
✓ 43-037-16221-00-00	PATARA OIL & GAS LLC	BIG INDIAN 4	Shut-In	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SWSW	14	30S-25E 5
✓ 43-037-16237-00-00	PATARA OIL & GAS LLC	LISBON A-715	Inactive	Water Disposal Well	LISBON	SAN JUAN	SWNW	15	30S-24E 6
✓ 43-037-16240-00-00	PATARA OIL & GAS LLC	LISBON B-613	Shut-In	Oil Well	LISBON	SAN JUAN	NENW	13	30S-24E 7
✓ 43-037-16242-00-00	PATARA OIL & GAS LLC	LISBON B-616	Shut-In	Oil Well	LISBON	SAN JUAN	NESW	16	30S-24E 8
✓ 43-037-16244-00-00	PATARA OIL & GAS LLC	BELCO ST 4 (LISBON B-816)	Active	Water Disposal Well	LISBON	SAN JUAN	NESW	16	30S-24E 9
✓ 43-037-16245-00-00	PATARA OIL & GAS LLC	LISBON C-69	Shut-In	Oil Well	LISBON	SAN JUAN	NWNE	9	30S-24E 10

✓ 43-037-16247-00-00	PATARA OIL & GAS LLC	LISBON C-94	Shut-In	Oil Well	LISBON	SAN JUAN	SWSE	4	30S-24E 11
✓ 43-037-16250-00-00	PATARA OIL & GAS LLC	LISBON UNIT D-84	Shut-In	Oil Well	LISBON	SAN JUAN	NESE	4	30S-24E 12
✓ 43-037-16251-00-00	PATARA OIL & GAS LLC	LISBON D-89	Shut-In	Oil Well	LISBON	SAN JUAN	NESE	9	30S-24E 13
43-037-16469-00-00	PATARA OIL & GAS LLC	LISBON U B-610	Producing	Oil Well	LISBON	SAN JUAN	NENW	10	30S-24E 14
43-037-16471-00-00	PATARA OIL & GAS LLC	NW LISBON USA A-2 (D-810)	Producing	Gas Well	LISBON	SAN JUAN	NESE	10	30S-24E 15
43-037-30054-00-00	PATARA OIL & GAS LLC	LISBON B-84	Shut-In	Oil Well	LISBON	SAN JUAN	NESW	4	30S-24E 16
43-037-30082-00-00	PATARA OIL & GAS LLC	LISBON B-814	Active	Water Disposal Well	LISBON	SAN JUAN	NESW	14	30S-24E 17
43-037-30317-00-00	PATARA OIL & GAS LLC	FEDERAL 15-25	Shut-In	Gas Well	WILSON CANYON	SAN JUAN	SWSE	25	29S-23E 18
43-037-30693-00-00	PATARA OIL & GAS LLC	LISBON C-99	Shut-In	Oil Well	LISBON	SAN JUAN	SWSE	9	30S-24E 19
43-037-30694-00-00	PATARA OIL & GAS LLC	LISBON U D-610	Shut-In	Gas Well	LISBON	SAN JUAN	NENE	10	30S-24E 20
43-037-30695-00-00	PATARA OIL & GAS LLC	LISBON B-94	Shut-In	Oil Well	LISBON	SAN JUAN	SESW	4	30S-24E 1
43-037-31014-00-00	PATARA OIL & GAS LLC	LISBON UNIT A-911	Producing	Gas Well	LISBON	SAN JUAN	SWSW	11	30S-24E 2
43-037-31034-00-00	PATARA OIL & GAS LLC	LISBON UNIT D-716	Shut-In	Oil Well	LISBON	SAN JUAN	SENE	16	30S-24E 3
43-037-31323-00-00	PATARA OIL & GAS LLC	LISBON C-910	Shut-In	Oil Well	LISBON	SAN JUAN	SWSE	10	30S-24E 4
43-037-31351-00-00	PATARA OIL & GAS LLC	LISBON B-614A	Shut-In	Oil Well	LISBON	SAN JUAN	NENW	14	30S-24E 5
43-037-31433-00-00	PATARA OIL & GAS LLC	LISBON B-810	Producing	Oil Well	LISBON	SAN JUAN	NESW	10	30S-24E 6

43-037-31829-00-00	PATARA OIL & GAS LLC	BIG INDIAN 35-24	Shut-In	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SENE	35	29S-24E 7
43-037-31831-00-00	PATARA OIL & GAS LLC	BULL HORN U 10-43	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SWSE	10	30S-25E 8
43-037-31838-00-00	PATARA OIL & GAS LLC	MIDDLE MESA ST 36-14-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NENE	36	29S-24E 9
43-037-31843-00-00	PATARA OIL & GAS LLC	BULL HORN FED 9-14-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NENE	9	30S-25E 30
43-037-31848-00-00	PATARA OIL & GAS LLC	BULL HORN FED 15-14-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NENE	15	30S-25E 1
43-037-31849-00-00	PATARA OIL & GAS LLC	BULL HORN FED 10-21-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NWSW	10	30S-25E 2
43-037-31850-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 14-21-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SWNW	14	30S-25E 3
43-037-31853-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 5-6-30-25	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	LOT6	5	30S-25E 4
43-037-31854-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 31-31-29-25	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NWSW	31	29S-25E 5
43-037-31855-00-00	PATARA OIL & GAS LLC	MIDDLE MESA ST 36-12-29-24	Shut-In	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NENW	36	29S-24E 6
43-037-31856-00-00	PATARA OIL & GAS LLC	MIDDLE MESA ST 36-24-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SENE	36	29S-24E 7
43-037-31859-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 15-24-30-25	Shut-In	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SWNW	14	30S-25E 8
43-037-31860-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 14-42-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SESW	14	30S-25E 9
43-037-31861-00-00	PATARA OIL & GAS LLC	BULL HORN FED 10-42-30-25	Shut-In	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SESW	10	30S-25E 40
43-037-31864-00-00	PATARA OIL & GAS LLC	BULL HORN FED 10-31-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NWSW	10	30S-25E 1
43-037-31877-00-00	PATARA OIL & GAS LLC	MIDDLE MESA ST 36-12B-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NENW	36	29S-24E 2

43-037-31878-00-00	PATARA OIL & GAS LLC	MIDDLE MESA ST 36-24B-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SENE	36	29S-24E ³
43-037-31883-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 15-24B-30-25	Shut-In	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	SWNW	14	30S-25E ⁴
43-037-31884-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 23-13B-30-25	Approved permit (APD); not yet spudded	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NWNE	23	30S-25E ⁵
43-037-31885-00-00	PATARA OIL & GAS LLC	BIG INDIAN FED 23-13-30-25	Approved permit (APD); not yet spudded	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NWNE	23	30S-25E ⁶
43-037-31891-00-00	PATARA OIL & GAS LLC	BULL HORN FED 15-13-30-25	Producing	Gas Well	BIG INDIAN (HERMOSA)	SAN JUAN	NENE	15	30S-25E ⁷
43-037-31893-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 30-41-29-25	Approved permit (APD); not yet spudded	Gas Well	UNDESIGNATED	SAN JUAN	SWSW	30	29S-25E ⁸
43-037-31897-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 5-10-30-25	Spudded (Drilling commenced: Not yet completed)	Gas Well	SOUTH PINE RIDGE	SAN JUAN	LT10	5	30S-25E ⁹
43-037-31901-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 25-43-29-24	Approved permit (APD); not yet spudded	Gas Well	UNDESIGNATED	SAN JUAN	SWSE	25	29S-24E ¹⁰
43-037-31902-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 25-41-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SWSW	25	29S-24E ¹
43-037-31903-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 25-31-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NWSW	25	29S-24E ²
43-037-31904-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 26-34-29-24	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NESW	26	29S-24E ³


43-037-31905-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 26-23-29-24	Approved permit (APD); not yet spudded	Gas Well	UNDESIGNATED	SAN JUAN	SWNE	26	29S-24E 4
43-037-31906-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 31-44-29-25	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SESE	31	29S-25E 5
43-037-31907-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 31-33-29-25	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NWSE	31	29S-25E 4
43-037-31909-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 31-22-29-25	Approved permit (APD); not yet spudded	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SENW	31	29S-25E 7
43-037-31910-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 31-11-29-25	Approved permit (APD); not yet spudded	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NWNW	31	29S-25E 8
43-037-50008-00-00	PATARA OIL & GAS LLC	CISCO STATE 36-13	Temporarily-Abandoned	Gas Well	WILDCAT	SAN JUAN	NWNE	36	31S-24E 9
43-037-50010-00-00	PATARA OIL & GAS LLC	MIDDLE MESA FED 4-20-30-25	Producing	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SWNW	4	30S-25E 60
43-037-50012-00-00	PATARA OIL & GAS LLC	Lisbon 11-32MC	Returned APD (Unapproved)	Oil Well	UNDESIGNATED	SAN JUAN	SWNE	11	30S-24E 1
43-037-50013-00-00	PATARA OIL & GAS LLC	Lisbon 14-11MC	Approved permit (APD); not yet spudded	Oil Well	LISBON	SAN JUAN	NWNW	14	30S-24E 2
43-037-50014-00-00	PATARA OIL & GAS LLC	Lisbon 10-44MC	Approved permit (APD); not yet spudded	Oil Well	LISBON	SAN JUAN	NWNW	14	30S-24E 3

43-037-50015-00-00	PATARA OIL & GAS LLC	Lisbon 3-32MC	Approved permit (APD); not yet spudded	Oil Well	LISBON	SAN JUAN	NESE	4	4 30S-24E
43-037-50016-00-00	PATARA OIL & GAS LLC	Lisbon 11-33MC	Approved permit (APD); not yet spudded	Oil Well	LISBON	SAN JUAN	NENW	14	5 30S-24E
43-037-50017-00-00	PATARA OIL & GAS LLC	Lisbon 11-21MC	Approved permit (APD); not yet spudded	Gas Well	LISBON	SAN JUAN	NWSE	10	6 30S-24E
43-037-50018-00-00	PATARA OIL & GAS LLC	Lisbon 3-43MC	Approved permit (APD); not yet spudded	Oil Well	LISBON	SAN JUAN	SESE	3	7 30S-24E
43-037-50019-00-00	PATARA OIL & GAS LLC	Lisbon 10-33MC	Spudded (Drilling commenced: Not yet completed)	Oil Well	LISBON	SAN JUAN	NWSE	10	8 30S-24E
43-037-50021-00-00	PATARA OIL & GAS LLC	Middle Mesa Fed 31-42-29-25	Approved permit (APD); not yet spudded	Gas Well	SOUTH PINE RIDGE	SAN JUAN	SESW	31	9 29S-25E
43-037-50026-00-00	PATARA OIL & GAS LLC	Middle Mesa Federal 5-8-30-25	Approved permit (APD); not yet spudded	Gas Well	SOUTH PINE RIDGE	SAN JUAN	NENE	5	10 30S-25E

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-89097
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: CCI PARADOX UPSTREAM, LLC		7. UNIT or CA AGREEMENT NAME: BIG INDIAN
3. ADDRESS OF OPERATOR: 600 17th Street, Suite 1900S , Denver, CO, 80202		8. WELL NAME and NUMBER: BIG INDIAN FED 14-42-30-25
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1292 FSL 1361 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SESW Section: 14 Township: 30.0S Range: 25.0E Meridian: S		9. API NUMBER: 43037318600000
PHONE NUMBER: 303 728-2222 Ext		9. FIELD and POOL or WILDCAT: BIG INDIAN (HERMOSA)
COUNTY: SAN JUAN		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 1/5/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: Site Facility Diagram	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Attached is the updated Site Facility Diagram. Thank you.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY February 02, 2015		
NAME (PLEASE PRINT) Ashley Noonan	PHONE NUMBER 303 728-2232	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 1/30/2015	

CCI Paradox Upstream LLC
Site Security Diagram
Wellsite: Big Indian 4
Sec.14, T30s, R25e
San Juan County, Utah
API# 43-037-16221
Lease# USA U-089097

CCI Paradox Upstream LLC
Site Security Diagram
Wellsite: Big Indian Federal 14-42
Sec.14, T30s, R25e
San Juan County, Utah
API# 43-037-31860
Latitude:38.174316
Longitude:-109.150827
Lease# UTU 89097



NOTE:

1. DRAWING IS NOT TO SCALE
2. ACTUAL PHYSICAL LOCATION OF UNDERGROUND FLOW LINES MAY NOT BE REPRESENTED ON THIS DRAWING. MAKE ONE CALL AND USE PIPE LOCATOR PRIOR TO DIGGING.

THIS LEASE IS SUBJECT TO THE SITE SECURITY PLAN.
THE PLAN IS LOCATED AT: Castleton Commodities International LLC
LISBON PLANT
7 RANKINE ROAD
LA SAL, UTAH 84530

GENERAL SEALING OF VALVES, SALES BY TANK GAUGING

Production Phase: All drain valves, D1, D2 and sales valve, S1, will be sealed closed during production. Fill valve F1 will be open.
Sales Phase: Drain valve D1, D2 and fill valve F1, will be sealed closed. The sales valve S1, will be closed and re-sealed after completion of sales activities. Fill valve F1 will be opened after completion of sales activities.
Draining Phase (from drain valves): Sales valve, S1 & S2 will be sealed closed during draining. The drain valves D1 or D2 will be closed and re-sealed after completion of draining activities.
Draining Phase (from sales valves): Drain valves, D1 & D2 will be sealed closed during draining. The sales valve S1 or S2 will be closed and re-sealed after completion of draining activities.

Site diagram and plan are available during normal working hours.